

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-11372-00-00  
Spot: NENENE Sec/Twnshp/Rge: 2-35S-2E  
4950 feet from S Section Line, 330 feet from E Section Line  
Lease Name: HOMESTEAD Well #: 2  
County: SUMNER Total Vertical Depth: 3525 feet

Operator License No.: 32887  
Op Name: ENDEAVOR ENERGY RESOURCES, LP  
Address: 110 N MARIENFELD, STE 200  
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3525		0 SX
SURF	8.625	150		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/26/2015 8:00 AM  
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC  
Proposal Rcvd. from: JOE DRISKILL Company: ENDEAVOR ENERGY RESOURCES, Phone: (918) 467-3111

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/18/2015 5:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

CIBP SET @ 3450'. CAPPED WITH 2 SX. SHOT PERFS. @ 250'. RAN IN 2 3/8" TUBING TO 280' PUMPED 135 SX OF 60/40 POS. MIX WITH 4% GEL. PULLED TUBING AND TOPPED OFF CSG WITH 15 SX. CAME BACK AND CUT OFF SURFACE CASING BELOW GROUND LEVEL. PLUGGING COMPLETE. ELITE CEMENTING TICKET #2545.

Perfs:

Top	Bot	Thru	Comments
3510	3512	TBG	


Remarks: PLUGGING OF WELL IS A RESULT OF A COMPLIANCE AGREEMENT BETWEEN OPERATOR AND COMMISSION, DOCKET #15-CONS-442-CMSC.

Plugged through: TBG

12/18/15  
CKM

District: 02

Signed



(TECHNICIAN)

KCC WICHITA

DEC 15 2015

RECEIVED