

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-22333-00-00
Spot: S2NENE Sec/Twnshp/Rge: 11-35S-2E
1050 feet from N Section Line, 550 feet from E Section Line
Lease Name: ANDERSON-WOODS Well #: 10
County: SUMNER Total Vertical Depth: 2258 feet

Operator License No.: 32887
Op Name: ENDEAVOR ENERGY RESOURCES, LP
Address: 110 N MARIENFELD, STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2255		125 SX
SURF	8.625	251		164 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/02/2015 12:00 AM
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Rcvd. from: JOE DRISKILL Company: ENDEAVOR ENERGY RESOURCES Phone: (918) 467-3111

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 09/15/2015 5:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

CIBP SET @ 2100' CAPPED W/ 2 SX. CSG WOULD NOT PRESSURE UP, POSSIBLE HOLE IN CASING. SET ANOTHER CIBP @ 1500' AND CAPPED W/2 SX. SHOT PERFS. AT 300', RAN IN 2 3/8" TUBING AND FINALLY BROKE CIRCULATION WITH 10 BBL'S OF WATER, PUMPED IN 70 SX OF 60/40 POS. MIX WITH 4% GEL UNTIL IT CIRCULATED TO SURFACE. PULLED TUBING, CUT OFF SURFACE CASING BELOW GROUND LEVEL. PLUGGING COMPLETE.

Perfs:

Top	Bot	Thru	Comments
2154	2160	TBG	

Remarks: PLUGGING OF WELL IS A RESULT OF A COMPLIANCE AGREEMENT BETWEEN OPERATOR AND COMMISSION, DOCKET #15-CONS-442-CMSC.

Plugged through: TBG

District: 02

Signed _____

Daniel Fox
(TECHNICIAN)

12/18/15 CKM

KCC WICHITA

DEC 15, 2015

RECEIVED