

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-47031-00-00
Spot: SENWSW Sec/Twnshp/Rge: 11-35S-2E
1650 feet from S Section Line, 4290 feet from E Section Line
Lease Name: STALNAKER/KUCHLER Well #: 2
County: SUMNER Total Vertical Depth: 3486 feet

Operator License No.: 32887
Op Name: ENDEAVOR ENERGY RESOURCES, LP
Address: 110 N MARIENFELD, STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2190		
PROD	5.5	2453		150 SX
SURF	8.5	103		0 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/02/2015 8:00 AM
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Rcvd. from: JOE DRISKILL Company: ENDEAVOR ENERGY RESOURCES, Phone: (918) 467-3111

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 09/17/2015 5:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

RAN IN 2190' OF 2 3/8" TUBING AND PUMPED IN 50 SX FOR BOTTOM PLUG, LET SET FOR A COUPLE OF HOURS, RAN IN AND TAGGED AT 1800' FOR TOP OF BOTTOM PLUG. SHOT PERFS. @ 250'. RAN IN 2 3/8" TUBING TO 280' PUMPED 125 SX OF 60/40 POS. MIX WITH 4% GEL. PULLED TUBING AND TOPPED OF CASING WITH 80 SX. CAME BACK AND CUT OFF SURFACE CSG. BELOW GROUND LEVEL. PLUGGING COMPLETE. ELITE CEMENTING TICKET #2543.

Perfs:

Top	Bot	Thru	Comments
2150	2162	TBG	


Remarks: PLUGGING OF WELL IS A RESULT OF A COMPLIANCE AGREEMENT BETWEEN OPERATOR AND COMMISSION, DOCKET #15-CONS-442-CMSC.

Plugged through: TBG

12/18/15 ckm

District: 02

Signed



(TECHNICIAN)

KCC WICHITA

DEC 15 2015

RECEIVED