

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-179-21094-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 5-10S-26W
350 feet from N Section Line, 380 feet from W Section Line
Lease Name: HAFFNER Well #: 1
County: SHERIDAN Total Vertical Depth: 4110 feet

Operator License No.: 32593
Op Name: HAFFNER, DAN
Address: RR 2 BOX 49
HOXIE, KS 67740

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4092		125 sx
SURF	8.625	226		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/16/2015 1:00 PM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: DAN HAFFNER Company: DAN HAFFNER Phone: (785) 324-2658

Proposed Plugging Method: DV Tool at 1499' w/270 sx cement.
Anh: 2256' - 2296'.
Production perforations: 3940' - 3941'.
Need to perforate at 2276'.
Run tubing to plug high fluid level.

Ordered 400 sx 60/40 pozmix 4% gel cement w/800 # hulls.

Plugging Proposal Received By: DARREL DIPMAN
Date/Time Plugging Completed: 11/16/2015 5:00 PM

WitnessType: COMPLETE (100%)
KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Perforated casing at 2276'. Ran tubing to 3903' and pumped 85 sx cement w/200 # hulls. Pulled tubing to 2654' and pumped 85 sx cement w/200 # hulls. Pulled tubing to 1342' and pumped 90 sx cement w/200 #hulls. Cement circulated. PTOH. Topped casing off w/20 sx cement. Casing full. Hooked to backside and pumped 15 sx cement. Shut in pressure 500 psi. Cement in casing dropped. Pumped another 50 sx cement. Casing full.

GPS: 39.21808 -100.25581

Remarks: GLOBAL CEMENTING

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

NOV. 23 2015
DEC 09 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS