

TO:

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-22585-00-01

Spot: SESESE

Sec/Twnshp/Rge: 11-24S-9E

300 feet from S Section Line, 600 feet from E Section Line

Lease Name: OLSON-ANDERSON

Well #: 29

County: GREENWOOD

Total Vertical Depth: 2233 feet

Operator License No.: 3599

Op Name: JB NORDMEYER, LLC DBA OLSON-AN

Address: 2253 P RD  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2258		150 SX
SURF	8.625	125		75 SX

Well Type: EOR

UIC Docket No: E25475.1

Date/Time to Plug: 11/19/2015 9:00 AM

Plug Co. License No.: 99973

Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC

Proposal Rcvd. from: BARNEY NORDMEYER

Company:

Phone: (620) 583-7548

Proposed Pump cement 50'. Plug above Bartlesville. Perforate casing 75' above Douglas. Pump 50' plug above Douglas formation.  
Plugging As we have already cemented on the backside of 4 1/2" casing from 205' to surface with cement on 9/9/1988, we will  
Method: cement inside of 4 1/2" from 200' to surface.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: PARTIAL

Date/Time Plugging Completed: 11/19/2015 1:00 PM

KCC Agent: MICHAEL HEFFERN

**Actual Plugging Report:**

ran tubing to 2095' pumped 15 sxs cement, pulled tubing to 934' pumped 15 sxs cement, pulled tubing to 220' pumped 25 sxs cement to surface, casing shot @ 934' & 220', gel spacers between cement plugs.

**Perfs:**

Top	Bot	Thru	Comments
2176	2184		
RECEIVED KCC DIST # 3 DEC 08 2015 CHANUTE, KS MH			

Remarks:

Plugged through: TBG

12/18/15 CCM

District: 03

Signed Mike D. [Signature]  
(TECHNICIAN)

Received Form CP-2/3  
KANSAS CORPORATION COMMISSION

DEC 10 2015

CONSERVATION DIVISION  
WICHITA, KS

810 E 7<sup>TH</sup>  
PO Box 92  
EUREKA, KS 67045  
(620) 583-5561



# Cement or Acid Field Report

Ticket No. **2624**  
Foreman Rick Ledford  
Camp Eureka KS

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
11-19-15	1087	Olsen - Anderson #29	11	24	10	GW	KS
Customer <u>John Nordmeyer</u>			Unit #		Driver		
Mailing Address <u>2253 P. Road</u>			104		<u>Alan A.</u>		
City <u>Eureka</u>			112		<u>Allen B.</u>		
State <u>KS</u>			141		<u>Shannon F.</u>		
Zip Code <u>67045</u>							
Safety Meeting <u>RL Am AB SF</u>							

Job Type P.T.A Hole Depth \_\_\_\_\_ Slurry Vol. \_\_\_\_\_ Tubing 2 3/8"  
Casing Depth \_\_\_\_\_ Hole Size \_\_\_\_\_ Slurry Wt. 14" Drill Pipe \_\_\_\_\_  
Casing Size & Wt. 4 1/2" Cement Left in Casing \_\_\_\_\_ Water Gal/SK 7.0 Other \_\_\_\_\_  
Displacement \_\_\_\_\_ Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: Safety meeting. Rig up to 2 3/8" tubing. Plugging orders as follows:

15 sks @ 2095'  
15 sks @ 934'  
25 sks @ 220' to surface

"Thank You"

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	15	Mileage	3.95	59.25
C203	55 sks	60/40 Permox cement	12.75	701.25
C206	190"	40% gel	.20	38.00
C108A	2.36	ton mileage bulk trk	m/c	345.00
C113	2 hrs	80 Bbl JAC. TEL	85.00	170.00
C224	3,000 gals	city water	10.00/1000	30.00
C206	400"	gel-spacers	.20	80.00
			7.50%	Subtotal
			Sales Tax	2173.50

Authorization witnessed by Barney Nordmeyer Title \_\_\_\_\_ Total \_\_\_\_\_

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.