

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-153-20385-00-01  
Spot: NESWSWSE Sec/Twnshp/Rge: 16-5S-32W  
465 feet from S Section Line, 2220 feet from E Section Line  
Lease Name: DECKER OWWO Well #: 1-16  
County: RAWLINS Total Vertical Depth: 4535 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4527		
SURF	8.625	391		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/06/2015 11:00 AM  
Plug Co. License No.: 34787 Plug Co. Name: GREEN OIL FIELD SERVICES, LLC  
Proposal Rcvd. from: MIKE KASSELMAN Company: L D DRILLING INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 445 sx 60/40 pozmix 4% gel cement, 600 # hulls and 600 # gel.  
8 5/8" surface casing set at 391' w/250 sx cement.  
4 1/2" production casing set at 4527' w/230 sx cement.  
TD 4535'. PBTD 4510'.  
Perforations: 4322' - 4324' and 4287' - 4290'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/10/2015 2:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 2665' and 1795'. Ran tubing to 4300' and pumped 600 # gel followed by 75 sx cement w/250 # hulls. Pulled tubing to 2660' and pumped 90 sx cement w/150 # hulls. Pulled tubing to 1330' and pumped 160 sx cement w/150 # hulls. Cement circulated to surface. Pulled tubing to surface. Connected to 8 5/8" surface casing and pumped 70 sx cement. Connected to 4 1/2" casing and pumped 50 sx cement. Cement falling.  
11/10/2015- Topped off 4 1/2" production casing with 2.75 yards of neat cement.

GPS: 39.61289N -100.91605W

Perfs:

Top	Bot	Thru	Comments
4322	4324		
4287	4290		

Remarks: GLOBAL OILFIELD SERVICES TICKET # 2521

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

12/18/15 ckm

DEC 01 2015

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

DEC 09 2015

CONSERVATION DIVISION  
WICHITA, KS