

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-189-30100-00-00  
Spot: NENESWNE Sec/Twnshp/Rge: 28-31S-38W  
1325 feet from N Section Line, 1324 feet from E Section Line  
Lease Name: LEONARD Well #: C-2  
County: STEVENS Total Vertical Depth: 3040 feet

Operator License No.: 32787  
Op Name: KANSAS NATURAL GAS OPERATING,  
Address: 1200 MAIN ST PO BOX 818  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2725		WITH 5 SX CMT
PROD	5.5	3039	0	WITH 800 SX CMT
SURF	8.625	612		WITH 325 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/04/2015 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: STEVE LEHNING Company: KANSAS NATURAL GAS Phone: (620) 675-8185

Proposed Plugging Method: SET CIBP @ 2725' WITH 2 SX CMT. PLUG AT 1740' WITH 30 SX CMT. CIRCULATE CMT FROM 660' TO SURFACE. CHECK BACKSIDE WITH CMT TO 300 PSI.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/04/2015 1:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 2725' WITH 5 SX CMT. 1ST PLUG AT 1740' WITH 30 SX CMT. 2ND PLUG AT 660' WITH 75 SX CMT TO 0'. CHECK BACKSIDE WITH 5 SX CMT TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
2897	2911		
2873	2885		
2821	2862		
2775	2810		

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_

*SA*

*Kenny Sullivan*

*12/18/15 CKM*

RECEIVED  
DEC - 8 2015  
KCC DODGE CITY

(TECHNICIAN)  
Received  
KANSAS CORPORATION COMMISSION

DEC 09 2015

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3