

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Reno County. Sec. 20 Twp. 22 Rge. 8 (E) (W) X

Location as "NE/CNW%SW%" or footage from lines C NW NW

Lease Owner Mull Drilling Company, Inc.

Lease Name Grover Well No. 2

Office Address 1625 Wichita Plaza Building Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 8-8-66 19

Application for plugging approved 8-9-66 19


Plugging commenced 8-9-66 19

Plugging completed 8-14-66 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3606 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	666239	None
				4 1/2	None	3216'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in unit. Started to clean out cellar.

Finished cleaning out cellar. Sanded to 3580'. Dumped 1/2 sacks of cement. Working pipe.

Working pipe. Shot pipe at 3200'. Pulling pipe.

Pulling pipe.

Pulling pipe. Plugging well. Set rock bridge at 225'. Dumped 20 sacks of cement. Filled hole and rock bridge. Capped well with 10 sacks.

8-22-66

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 1966

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17 day of August, 19 66

My commission expires May 27, 1969

Notary Public

ROTARY DRILLERS LOG

COMPANY: Mull Drilling Co., Inc. et al
Wichita, Kansas
CONTRACTOR: Mull Drilling Co., Inc.
Wichita, Kansas
CASING RECORD: Set 239' of 8 5/8" cas. w/175 cu
Set 4 1/2" cas. @ 3606' w/100 cu

ROTARY DRILLING COMMENCED: 2/18/66
ROTARY DRILLING COMPLETED: 2/25/66
LOCATION: GROVER #3
C 1/4 NW 20-22S-8W
Reno County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Boring)

- 1200' Shale w/shells
- 1235' Shale w/lime
- 2512' Lime & Shale
- 2551' Chert
- 3381' Conglomerate
- 3610' Kinderhook - total depth

8-26-66
RECEIVED
STATE CORPORATION COMMISSION
AUG 26 1966

I hereby certify that this is a true and correct copy of the above of my knowledge.


CONSERVATION DIVISION
Wichita, Kansas

MULL DRILLING COMPANY, INC.

Delbert J. Jordan
Delbert J. Jordan, Geologist

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

and sworn to before me this 24th day of May, 1966.



Walter J. ...
Walter J. ...

an engineer: Feb. 24, 1966