


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Reno County. Sec. 2 Twp. 22 S Rge. 9 E/W  
Location as "NE/CNW/SW" or footage from lines  
C SW NE  
Lease Owner Hummon Oil Co.  
Lease Name Bennett Well No. 1  
Office Address 1725 Vickers Bldg., Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above  
Section Plat

Date Well completed July 28, 19 76  
Application for plugging filed July 28 19 76  
Application for plugging approved July 28 19 76  
Plugging commenced July 28 19 76  
Plugging completed July 28 19 76  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Joman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3470  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom plug set at 500' with 40 sacks 50/50 Pozmix thru drill pipe (2% Gel)  
Middle Plug set at 190' with 25 sacks 50/50 Pozmix, 2% Gel, thru drill pipe  
Top Plug set at 40' with 1/2 sack hulls and 10 sacks cement  
2 sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 30 1976

(If additional description is necessary, use BACK OF THIS SHEET)

Name of Plugging Contractor Duke Drilling Co.  
Box 823 - Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.  
Wayne Dobbs (employee of owner) or (~~owner or operator~~)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne Dobbs  
Box 823 - Great Bend, Ks. 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of July, 19 76

Meredy M. Waque  
Notary Public.

My commission expires April 11, 1978

Drillers' Well Log

Date Commenced: July 21, 1976  
Date Completed: July 28, 1976

Hummel Oil Company  
"Bennett #1"  
C. SW. NE  
Sec. 2-3225-2911  
Reno County, Kansas

Elevations 1687 R.E.

- 0 - 100' Clay & Sand
- 100 - 274' Red Bed
- 274 - 291' Anhydrite
- 291 - 2540' Shale
- 2540 - 2575' Sand
- 2575 - 2877' Lime & Shale
- 2877 - 2881' Shale
- 2881 - 3027' Shale & Lime
- 3027 - 3051' Lime & Shale
- 3051 - 3378' Lime
- 3378 - 3470' Lime, Shale, Chert
- 3470' RJD

Formation Data

Anhydrite	274
Heebner	2877
Brown Lime	3027
Lansing	3051
Base L.C.	3378
Conglomerate	3430
RJD	3470

Surface Pipe: Set used 8-5/8",  
28" pipe at 199' with 140 sacks  
common, 2% Gel, 3% cc.

Affidavit

State of Kansas  
County of Barton ss.

Wayne Dobbs, of lawful age does swear and state that the facts and statements  
herein contained are true and correct to the best of his knowledge.

Wayne Dobbs

Subscribed and sworn to before me this 28 day of July 1976.

My Comm. Expires  
April 11, 1978

Clairdy M. Sague  
Notary Public

RECEIVED

7-30-76

JUL 30 1976

CONCEIT M. WILLIAMS, JR.  
Notary Public