


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Reno County. Sec. 30 Twp. 22 Rge. 8 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines C. SE NW

Lease Owner Mull Drilling Co. Inc.
Lease Name Morgan B-1 Well No. ###
Office Address 670 N. 14th. Natl. Bank Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole.
Date well completed 9-28 1961
Application for plugging filed 9-28 1961
Application for plugging approved 9-28 1961
Plugging commenced 8:00 P.M. 9-28 1961
Plugging completed 9:00 P.M. 9-28 1961
Reason for abandonment of well or producing formation
Non Productive.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3630' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with drilling mud to within 230' of top and a plug was put at this depth with 1/4 sack hulls put on top of plug. 20 sacks cement was then added. Hole was then filled to within 30' of top and a plug was added at this depth with 1/4 sack hulls. 10 sacks cement was put on this, completing the plugging. Rat hole was bridged and 2 sacks cement was added plugging same.

RECEIVED
STATE CORPORATION COMMISSION
OCT 10 1961
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Co. tools.
Address Same as above.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Joseph O. Butts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph O. Butts
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of October, 19 61

My commission expires January 28, 1965
Ethel Zimmerman Notary Public.



ROTARY DRILLERS LOG

COMPANY: Mull Drilling Co., Inc. Et al
Wichita, Kansas

ROTARY DRILLING COMMENCED: 9/21/61

CONTRACTOR: Mull Drilling Co., Inc.
Wichita, Kansas

ROTARY DRILLING COMPLETED: 9/28/61

CASING RECORD: Set 268' of 8 5/8" w/205 sx cnt.
D & A

LOCATION: MORGAN "B" #1
C SE NW 30-22S-8W
Reno County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing.)

650'	Red Bed
1100'	Shale & Shells
2172'	Lime & Shale
2600'	Sandy Lime & Shale
3566'	Lime & Shale
3630'	Mississippi Chert - total depth

RECEIVED
STATE GOVERNMENT
OCT 4 1961
CONSERVATION DIVISION
Wichita, Kansas


I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

D. J. Costa
D. J. Costa, Geologist

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 3rd day of October, 1961.



Madeline N. Miller
Notary Public