


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Reno County. Sec. 30 Twp. 22S Rge. 8W EA
Location as "NE/CNW $\frac{1}{2}$ /SW $\frac{1}{2}$ " or footage from lines C-NE SE

Lease Owner K.R.M. Petroleum Corporation
Lease Name R. L. Flickinger Well No. 1
Office Address Guaranty Bank Bldg., 817 17th St., Denver
Character of Well (Completed as Oil, Gas or Dry Hole) CO 80202



Locate well correctly on above
Section Flat

Dry Hole
Date Well completed January 4, 1980
Application for plugging filed Verbal Application 1980
Application for plugging approved Verbal Approval 1980
Plugging commenced January 4, 1980
Plugging completed January 4, 1980
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 1980

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,700'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 357' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,700 ft. (rotary total depth) to 360 ft. Set plug at 360 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 360 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent (~~XXXXXX~~ of owner) ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 N. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of January, 1980

My commission expires July 25, 1982
Elsie Willison
Elsie Willison - Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
1-10-80
JAN 10 1980
CONSERVATION DIVISION
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY K.R.M. Petroleum Corporation

SEC. 30 T. 22S R. 8W
LOC. C-NE SE

FARM R. L. Flickinger NO. 1

COUNTY Reno

ROTARY TOTAL DEPTH 3,700'
COMM. December 27, 1979 COMP. January 4, 1980
CONTRACTOR H-30, INC. (Rig #7)
ISSUED January 8, 1980

CASING

10 3/4"
8 5/8" Set at 363' cemented w/300 bxs cement
5 1/2"
4 1/2"

ELEVATION 2,001' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

| | |
|------------------------|--------|
| Sand and Shale | 367' |
| Shale and Shells | 1,551' |
| Shale, Shells and Lime | 1,891' |
| Lime and Shale | 2,510' |
| Shale and Lime | 2,584' |
| Lime and Shale | 2,970' |
| Shale and Lime | 3,189' |
| Lime and Shale | 3,465' |
| Lime | 3,579' |
| Lime and Shale | 3,700' |
| Rotary Total Depth | 3,700' |

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 9th day of January, 1980.

WILLIS
NOTARY

Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982

1-10-80
RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1980
CONSERVATION DIVISION
Wichita, Kansas