


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Reno County. Sec. 31 Twp. 22 Rge. 8 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C NE SE
Lease Owner Mull Drilling Co. Inc.
Lease Name Rupp Well No. 1
Office Address 670 N. 4th. Natl Bank Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole.
Date well completed 10-28-61 19
Application for plugging filed 10-28-61 19
Application for plugging approved 10-28-61 19
Plugging commenced 9:00 A.M. 10-28-61 19
Plugging completed 10:00 A.M. 10-28-61 19
Reason for abandonment of well or producing formation
Non Productive.
If a producing well is abandoned, date of last production None. 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3720' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled to within 240' of top and a plug put at this depth with $\frac{1}{4}$ sack ~~hulls~~ put on top of plug. 18 sacks cement was put on top through drill pipe. Hole was then filled with mud to within 38' of top and a plug put at this depth with $\frac{1}{4}$ sack hulls put on top of plug. 10 sacks cement was then put on top and this filled surface pipe to the bottom of cellar. Two sacks cement was used to plug rat hole. This completed the plugging.

11-10-61
RECEIVED
STATE CORPORATION COMMISSION
NOV 10 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Co. tools.
Address Same as above.


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Joseph O. Butts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph O. Butts
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 7th day of November, 19 61

My commission expires October 16, 1965

Bettis H. Satter
Notary Public.



ROTARY DRILLERS LOG

COMPANY: Mull Drilling Co., Inc. et al
Wichita, Kansas

ROTARY DRILLING COMMENCED: 10/23/61

CONTRACTOR: Mull Drilling Co., Inc.
Wichita, Kansas

ROTARY DRILLING COMPLETED: 10/31/61

CASING RECORD: Set 8 5/8" @ 263' w/175 sx cmt
D & A

LOCATION: RUPP #1
C NE SE 31-22-8W
Reno County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing.)

680'	Red Bed
1250'	Shale & Shells
2555'	Lime & Shale
2755'	Sandy Lime & Shale
2998'	Lime & Shale
3140'	Sandy Lime & Shale
3482'	Lime & Shale
3605'	Lime
3652'	Lime w/Shale
3693'	Mississippi chert
3703'	Lime & chert
3720'	Kinderhook - total depth

RECEIVED
STATE CORPORATION COMMISSION
11-10-61
NOV 10 1961
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

D. J. Costa
D. J. Costa, Geologist

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 8th day of November, 1961.



Margaret M. Miller
Notary Public

Commission Expires: Feb. 24, 1964