


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Reno County, Sec. 7 Twp. 22S Rge. 9W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
660' FWL, 660' FNL, NW 1/4
Lease Owner Daskocil Sausage Company
Lease Name Drake #1 Well No. 1
Office Address 321 N. Main Street, South Hutchinson, Ks 67505
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole
Date Well completed April 13, 1977 19
Application for plugging filed April 13, 1977 19
Application for plugging approved April 13, 1977 19
Plugging commenced 11:30 AM, April 13, 1977 19
Plugging completed 2:00 PM, April 13, 1977 19
Reason for abandonment of well or producing formation
Dry Hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3640'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	213'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
40 sacks at 500'; 25 sacks at 200';
10 sacks 40' to surface; 2 sacks
in rat hole. 4-21-77

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor STERLING DRILLING COMPANY
P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner, Secretary
STERLING DRILLING COMPANY
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of April, 1977

CHARLES HALL—NOTARY PUBLIC My Commission Expires Jan. 6, 1978
Charles M. Hall, Notary Public.

My commission expires



STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- DRAKE #1

Located: 660' FWL, 660' FNL, NW/4, Section 7-22S-9W,
Reno County, Kansas

OWNER: Doskocil Sausage Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 6, 1977
COMPLETED: April 13, 1977

TOTAL DEPTH: 3640'

LOG

CASING RECORD

0 - 213 Sand, Red Shale
213 - 1420 Shale
1420 - 3640 Lime and Shale

Ran 7 joints 8 5/8", 24# casing, 200.75' set
at 213' K.B. Cemented with 175 sacks cement,
2% gel, 3% cc. Plug down at 8:00 PM, 4-6-77.
Plugged.

4-21-77

RECEIVED
STATE COMMISSION

APR 21 1977

COMMISSIONER
Topeka, Kansas