

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-21,025-

LEASE NAME Drake 0000

WELL NUMBER 1

SPOT LOCATION SE SW NW

SEC. 7 TWP. 22 SRGE. 9 (SE)

COUNTY Reno

Date Well Completed 11-16-84

Plugging Commenced 11-16-84
2:00 PM

Plugging Completed 11-16-84
4:15 PM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Zenith Drilling Corporation
ADDRESS Suite 505 Fourth Financial Center
Wichita, Kansas 67202

PHONE # (316) 265-6697 OPERATORS LICENSE NO. 5141

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 2

Is ACO-1 filed? If not, is well log attached? Yes

Producing formation Depth to top bottom T.D. 3690'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	271'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud.

Plugged with 35 sacks at 3684'; 35 sacks at 321';

1/2 sack Hulls, Howco plug for bridge at 40'; 15 sacks

40' to surface, 10 sacks in rathole. Used 50/50 Pozmix, 2% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) F. A. Wuellner
(Address) P. O. Box 129, Sterling, Kansas 67579



SUBSCRIBED AND SWORN TO before me this 19 day of November, 1984

Agnes D. Wurst
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-85

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - DRAKE #1

Located: SE SW NW, Section 7-22S-9W, Reno County, Kansas

OWNER: Zenith Drilling Corporation

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 11, 1984

COMPLETED: November 16, 1984

TOTAL DEPTH: 3690'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 165 Sand	Ran 6 joints 8 5/8", 20# casing. 258.29'
165 - 281 Red Shale	pipe set at 271' K.B. Cemented with 200
281 - 960 Shale	sacks Common, 2% gel and 3% cc. Plug down
960 - 980 Anhydrite	at 5:00 PM, 11-11-84, by Howco.
980 - 3690 Lime and Shale	Plugged.

Deviation Surveys: 1° at 1690'
1° at 3633'