


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Reno County, Sec. 12 Twp. 22S Rge. 9 (W)
Location as "NE/CNW/SW" or footage from lines C SW NW
Lease Owner Sterling Drilling Company
Lease Name Proffitt Well No. 1
Office Address Box 127, Sterling, Kansas 67579
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 3 1966
Application for plugging filed September 3 1966
Application for plugging approved September 3 1966
Plugging commenced 1:00 a.m. September 3 1966
Plugging completed 3:00 a.m. September 3 1966
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Hugh E. Scott, McPherson, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3885 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Casing	0	224	7"	X	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 200', Halliburton plug, 1/4 sack hulls, 20 sacks cement; filled hole with heavy mud to 140', Halliburton plug, 1/4 sack hulls, 10 sacks cement up to the base of cellar; bridge rat hole and 2 sacks cement.

9-9-66

RECEIVED
STATE CORPORATION COMMISSION

SEP 9 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company
Address Box 127, Sterling, Kansas 67579

STATE OF KANSAS, COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) F. A. Wuellner
Box 127, Sterling, Kansas F. A. Wuellner, Secretary
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of September, 1966

BERNARD LAUDERMILK, Notary Public
My commission expires Commission Expires January 22, 1970

Bernard Laudermilk
Bernard Laudermilk, Notary Public.

STERLING DRILLING COMPANY
Sterling, Kansas

WELL LOG - - - - - PROFFITT #1
LOCATED: C SW NW Section 12-228-9W, Reno County, Kansas

OWNER: Sterling Drilling Company, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 25, 1966
COMPLETED: September 3, 1966

ROTARY TOTAL DEPTH: 3885'

LOG

0 - 160	Sand & Shale
160 - 225	Red Bed
225 - 1648	Sand & Shale
1648 - 1785	Lime
1785 - 3130	Shale & Lime
3130 - 3285	Lime
3285 - 3460	Lime & Shale
3460 - 3515	Lime & Chert
3515 - 3885	Lime & Shale T.D.

CASING RECORD

Ran 7 joints 7" 20# used seamless casing. 211.83' pipe set at 224' K.B. Cemented with 100 sacks 50 X 50 Pozmix with 2% HA-5. Plug was down at 1:30 a.m. by Sun Oil Company.

Plugged as follows: Heavy mud up to 200', Halliburton plug, 1/4 sack hulls, 20 sacks cement; heavy mud up to 40', Halliburton plug, 1/4 sack hulls, 10 sacks cement up to the base of cellar; bridge rat hole, 2 sacks cement. Plug was down at 3:00 a.m. 9-3-66.

9-9-66
RECEIVED
STATE CORPORATION COMMISSION

SEP 9 1966

CONSERVATION DIVISION
Wichita, Kansas