

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202  
DEC 2 1985

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER <sup>15</sup> 12-151-21,297  
LEASE NAME Shriver

WELL NUMBER #2  
SPOT LOCATION SE NE SE

SEC. 14 TWP. 29 RGE. 14 OE or (W)  
COUNTY Pratt

Date Well Completed 8-30-1983  
Plugging Commenced 11-19-85  
Plugging Completed 11-21-85

WICHITA OFFICE

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR The Reach Group  
ADDRESS 229 E. William, Suite 500, Wichita, Ks.

PHONE # (316) 262-1515 OPERATORS LICENSE NO. 8572

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks.

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation Lansing Depth to top 4143 bottom 4146 T.D. 4584

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				8 5/8"	452'	0'
Production				4 1/2"	4394'	2647'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls & 20 sks. cement to 3920'  
Pumped 50 sks. cement 800' to 650' - displaced w/mud to 480'  
Pumped 50 sks. cement 480' to 330' - displaced w/mud to 40'  
Put bridge & 10 sks. cement 40' to 0'  
Cut off 3' below ground level & cap 8 5/8"

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497  
Address Box F, Sublette, Ks. 67877

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Haskell, ss.

I, Edgar J. Eves (employee of operator) or operator of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves  
(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 26th day of Nov., 1985

Sandra L Eves  
Notary Public

My Commission expires: 12-6-88

