


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
1015 No. Broadway
Wichita, Kansas

15-151-191b1-60-60
40
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pratt County, Sec. 14 Twp. 29 Rge. 14W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SE SE
Lease Owner Nadel and Gussman Oil Producers
Lease Name Shriver Well No. 1
Office Address 625 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 4 1962
Application for plugging filed December 4 1962
Application for plugging approved December 4 1962
Plugging commenced December 4 1962
Plugging completed December 4 1962
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Herman Justus, Nickerson, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	779'	0	779'	8-5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole plugged as follows: Plugged at 775' with 25 sacks of cement through drill pipe, mud to 40'; plugged with 1/4 sack of hulls and cement to cellar. Job completed at 8:00 P. M. December 4, 1962.

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1962
12-21-62
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Ralph Schuyler (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph Schuyler
STRATA DRILLING, INC.
Ralph Schuyler
Box 355, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of December, 1962

My commission expires December 14, 1965
Elaine H. Taylor
Elaine H. Taylor, Notary Public.

DRILLERS LOG

#1 Shriver

CASING RECORD: 779' of used 8-5/8" surface casing.	COMPANY: Nadel and Gussman	DESCRIPTION: SW SE SE Section 14-29-14W Pratt Co., Kansas
TOTAL DEPTH: 4548'	CONTRACTOR: Strata Drilling, Inc.	ELEVATION: 1967' DF
	COMMENCED: November 21, 1962	
	COMPLETED: December 4, 1962	

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	207	Ran 779' of used 8-5/8" surface casing; set and cemented at 787' with 250 sacks of regular cement, 2% gel and 2% C. C.. Plug down at 3:30 P. M. November 22, 1962. Cement circ.
Shale & Red Bed	207	615	
Shale	615	1930	
Lime & Shale	1930	2105	
Lime	2105	2275	
Lime & Shale	2275	3985	
Lime	3985	4080	
Lime & Shale	4080	4140	
Lime	4140	4188	
Lime & Shale	4188	4265	
Lime	4265	4480	
Cherty Lime	4480	4515	
Lime	4515	4519	
Cherty Lime	4519	4525	
Lime, Shale & Sand	4525	4545	
Sand	4545	4548	

RECEIVED
STATE CORPORATION COMMISSION

DEC 17 1962

CONSERVATION DIVISION
Wichita, Kansas

D. & A.

Total Depth - 4548'

Plugged as follows; plugged at 775' with 25 sacks of cement through drill pipe, mud to 40'; plugged with 1/2 sack of hulls and cement to cellar. Job completed at 8:00 P. M. December 4, 1962.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Jim B. McWilliams
Jim B. McWilliams, Secy-Treas.

Subscribed and sworn to before me this 6th day of December, 1962.

Elaine H. Taylor
Elaine H. Taylor, Notary Public

My Commission Expires:

December 14, 1965