

RECEIVED

MAR 08 2002

KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-047-21276-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR American Energies Corporation KCC LICENSE # 5399
(owner/company name) (operator's)

ADDRESS 155 North Market, Suite 710 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 263-5785

LEASE Twitchell WELL# 3 SEC. 2 T. 24S R. 17W (East/West)

E/2. E/2 .NE SPOT LOCATION/OOOO COUNTY Edwards

1320 FEET (in exact footage) FROM S N (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE None SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8" SET AT 296 CEMENTED WITH 200 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4350 CEMENTED WITH 125 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perforations: 4290-4302

ELEVATION 2097 K.B. T.D. 4445 PBD 4350 ANHYDRITE DEPTH 1104
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING 50' Sand plug over perfs, 5 sx cement, pull 4 1/2" casing:

Fill hole with mud and gel to 1100', pump 40 sx cement, plug hole with

mud and gel to 350', pump 40 sx plug, place 10 sx cement, plug at surface

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Yes

If not explain why? Filed with ACO-1

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Lawrence W. Jackson, Production Superintendent PHONE# 620-793-2146

ADDRESS P.O. Box 1431 City/State Great Bend, KS

PLUGGING CONTRACTOR Gressel Oilfield Services KCC LICENSE # 3004
(company name) (contractor's)

ADDRESS P.O. Box 438, Haysville, Kansas PHONE # (316)-524-1225

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) As soon as possible.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3/7/02 AUTHORIZED OPERATOR/AGENT: Alan L. DeGood
(signature)

Alan L. DeGood, President

6/02

6/02



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

American Energies Corporation
155 N. Market, Ste 710
Wichita, KS 67202

March 18, 2002

Re: TWITCHELL #3-2
API 15-047-21276-00-00
CE2E2NE 2-24S-17W, 3960 FSL 330 FEL
EDWARDS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in black ink, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888