

1 050795

Docket No. D-19,240

To: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

API NUMBER 15- Completed as D & A 12-29-46

SE SE SE, SEC. 15, T 24 S, R 17 WAK

330 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5054

Lease Name David Britton Well # 2

Operator: F. G. Holl

County Edwards 161.43

Name & Address 6427 E. Kellogg

Well Total Depth 4967 feet

Address

Conductor Pipe: Size 16 feet 98

Wichita, KS 67207

Surface Casing: Size 10 3/4 feet 1064

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well ☒ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P. O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 9:00 am Day: 10 Month: April Year: 19 86

Plugging proposal received from Tom Pool

(company name) J. G. Holl (phone) 316-684-8481

were: 5 1/2" at 4765' Open Hole from 4765-4967 Perfs at 4320-34'

1st plug pump through tubing at 2800' with 250 sx cement (50/50 Pozmix 6% gel)

If cement is lost pump more.

2nd plug pump 3 sx hulls and 200 sx cement (Econolite) down 10 3/4"

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)Plugging Operations attended by Agent?: All ☒ Part _____ None _____

Operations Completed: Hour: 10:15 am Day: 10 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 4-7-86 - pumped through tubing at 2800' with 250 sx cement
(50/50 Pozmix 6% gel). Lost cement. Pumped 3 sx hulls and 50 sx cement. Tagged

cement at 2100'. J. H. Metz observed this portion and completed it at 5:45 pm 4-7-86.

4-10-86 - Pumped 3 sx hulls and 200 sx cement (Econolite) down 10 3/4".

Maximum pressure 700 psi and shut in 400 psi.

Remarks: Recovered 1491' 5 1/2" casing. Cemented by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

APR 16 1986

DATE

INV. NO. 13460

Signed Richard W. Lacey
(TECHNICIAN)