

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-055-00860-0000 Drill Completion Date -

API NUMBER 2/26/52
 LEASE NAME Bunnside A
 WELL NUMBER 1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

2490 Ft. from S Section Line
2790 Ft. from E Section Line

LEASE OPERATOR Ensign Operating Co.
 ADDRESS 621 17th St., Ste 1800; Denver, Co. 80293
 PHONE# (303) 293-9999 OPERATORS LICENSE NO. 4782

SEC. 29 TWP. 24 RGE. 32 (N or W)
 COUNTY Finney

Character of Well Gas
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)
 The plugging proposal was approved on JUN 7 1989 5/16/89 (date)

Date Well Completed 4/26/52
 Plugging Commenced 5/25/89
 Plugging Completed 5/25/89

by Richard W. Lacey CONSERVATION DIVISION (KCC District Agent's Name).
 Wichita, Kansas

Is ACO-1 filed? No If not, Is well log attached? Well log was filed with CP-1.

Producing Formation Chase Depth to Top 2518' Bottom 2582' T.D. 2676'

Show depth and thickness of all water, oil and gas formations. PBTD 2582'

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Ogallala</u>	<u>Water</u>	<u>275</u>	<u>400</u>	<u>10 3/4"</u>	<u>323'</u>	<u>None</u>
<u>Hecrington</u>	<u>Gas</u>	<u>2518</u>	<u>2530</u>	<u>7"</u>	<u>2558'</u>	<u>None</u>
<u>Krider</u>	<u>Gas</u>	<u>2544</u>	<u>2592</u>			
<u>Winfield</u>	<u>Gas</u>	<u>2605</u>	<u>2635</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Circulated hole with 100 bbla mud and 2 sx hulls; Spot 50 sx cmt from 2400' back to 1900'; Spot 50 sx cmt from 1450' back to 950'; and Spot 35 sx cmt from 335' back to 3'. Cut off and capped surface and production casing 3' below GL. Cement was 60/40 Pozmix, 2% gell by Halliburton.
 (If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Fast and Martin Well Service License No. 8438

Address P.O. Box 297; Garden City, Ks. 67846

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ensign Operating Co.; 621 17th St, Ste 1800

STATE OF Colorado COUNTY OF Denver, ss.

Reed A. Wacker (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Reed A. Wacker

(Address) Box 937; Garden City, Ks 67846

SUBSCRIBED AND SWORN TO before me this 5th day of June, 19 89

Iola L. Upchurch
 Notary Public

My Commission Expires: November 11, 1992