

15-079-20049-0000



Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Harvey County, Sec. 7 Twp. 24S Rge. (X) 2 (W)

Location as "NE/CNW%SW%" or footage from lines SE NE SW

Lease Owner Kern Drilling Co., Inc.

Lease Name Redinger Well No. 1

Office Address Box 699, Magnolia, Arkansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 5, 1968

Application for plugging filed April 5, 1968

Application for plugging approved April 5, 1968


Plugging commenced April 5, 1968

Plugging completed April 5, 1968

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott, McPherson, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3925 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	474'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Ran 23 stands of pipe in hole and spotted 50 sacks cement at 1420 feet. Layed down 11 stands of drill pipe and spotted 25 sacks cement at 450 feet. Out with 10 stands of drill pipe, spotted 10 sacks cement at 40 feet and put 5 sacks cement in rat hole all with pump truck.

4-10-68

RECEIVED  
STATE CORPORATION COMMISSION  
APR 10 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.

Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

John C. Graves (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *John C. Graves*

505 Union Center, Wichita, Kansas 67202

(Address)

SUBSCRIBED AND SWORN to before me this 9th day of April, 1968

*Betty Brandt*  
Betty Brandt Notary Public.

My commission expires May 9, 1971

15-079-20049-0000  
 RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 10 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

ROTARY DRILLERS' LOG

4-10-68

OPERATOR: Kern Drilling Co., Inc. DRILLING COMMENCED: March 27, 1968  
 Box 699  
 Magnolia, Arkansas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: April 5, 1968  
 505 Union Center  
 Wichita, Kansas

CASING RECORD: 19 Jts. 474' 8-5/8" LOCATION: Redinger No. 1  
 cemented with 350 sacks SE NE SW  
 Section 7-24S-2W  
 Harvey County, Kansas

0 - 245	Sand	2945 - 2992	Lime
245 - 471	Shale & shells	2992 - 3010	Shale & lime
471 - 482	Anhydrite	3010 - 3057	Lime & shale
482 - 630	Lime	3057 - 3329	Shale & lime
630 - 1405	Lime & shale	3329 - 3363	Sand & shale
1405 - 1476	Shale & sand	3363 - 3380	Lime & shale
1476 - 1635	Sand, lime & shale	3380 - 3540	Lime & cherty dolomite
1635 - 1930	Shale & lime	3540 - 3736	Lime
1930 - 2040	Lime & shale	3736 - 3769	Lime & shale
2040 - 2138	Shale & lime	3769 - 3779	Lime & dolomite
2138 - 2255	Lime & shale	3779 - 3810	Dolomite
2255 - 2298	Lime	3810 - 3846	Shale
2298 - 2370	Shale & lime	3846 - 3870	Shale & lime
2370 - 2490	Sandy shale	3870 - 3925	Sand
2490 - 2870	Lime	3925	Rotary Total Depth
2870 - 2945	Lime & shale		

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.  
 By [Signature]  
 President

STATE OF KANSAS )  
 ) SS:  
 SEDGWICK COUNTY )

Subscribed and sworn to before me, a Notary Public, this 9th day of April, 1968.

[Signature]  
 Betty Brandt Notary Public

My commission expires: May 9, 1971