

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202  
**NORTH**

## WELL PLUGGING RECORD

Harvey County. Sec. 18 Twp. 24 Rge. 3 (E) (W)  
Location as "NE/CNW&SW&" or footage from lines SW SW SW  
Lease Owner R. L. Evans  
Lease Name J. Hoskinson Well No. 1  
Office Address Harold J. Milburn, 3803 Panorama Dr. Hutchinson, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry 67501  
Date well completed April 29 19.70  
Application for plugging filed 19.  
Application for plugging approved 19.  
Plugging commenced 19.  
Plugging completed April 29, 19.70  
Reason for abandonment of well or producing formation Hole Dry  
  
If a producing well is abandoned, date of last production 19.  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Hugh Scott  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 1424 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

**CASING RECORD**

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug hole. Set bottom plug at 235 ft. and put in 35 sacks of cement. Set top plug at 30 ft. and put in 15 sacks of cement. Put 2 sacks of cement in rat hole. Plugging completed at 8:00 P. M., April 29, 1970. Plugging completed by Hugh Scott, McPherson, Kansas.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 8 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor BLACKSTONE DRILLING, INC.  
Address Box 455, McPherson, Kansas 67460

STATE OF Kansas, COUNTY OF Reno *Namey*, ss.  
Harold J. Milburn (employee of owner) or (owner or operator) of the above-described  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God. 10

(Signature) Carol J. Melburn  
3803 Panorama Dr. Hutchinson, Kansas 67501  
(Address)

Subscribed and Sworn to before me this

7th

-day of

My performance analysis

July 22, 1972

Notary Public.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON, KANSAS 67460

April 30, 1970

COMPANY: R. J. EVANS

CONTRACTOR: BLACKSTONE DRILLING, INC.

FARM: J. ROSKINSON #1

LOCATION: SW SW SW 16-24-38, Harvey County, Kansas

COMMENCED: April 21, 1970

COMPLETED: April 29, 1970

ELEVATION: 1455 K. B.

0	to	210	Sand
210	to	241	Shale
241	to	675	Shale & Linc
675	to	985	Linc & Shale
985	to	1225	Linc
1225	to	1570	Linc & Shale
1570	to	2180	Shale & Linc
2160	to	2395	Linc
2395	to	2635	Shale & Linc
2635	to	3090	Linc
3090	to	3280	Linc & Shale
3280	to	3400	Shale & Linc
3400	to	3700	Mississippi
3700	to	3735	Linc & Chert
3735	to	3783	Linc
3783	to	3845	Shale & Linc
3845	to	3910	Linc & Shale
3910	to	3932	Viola
3932	to	3965	Simpson
3965	to	4011	Sand & Linc
4011	to	4024	Arbuckle
		4024	T. D.


Cut 15 1/4 in. hole to 241 ft. and run 240 ft. of 10 3/4 in. surface pipe, cemented with 250 sacks at 241 ft., plug down at 4:30 P. M., April 21, 1970. Cut 7 7/8 in. hole to 4024 ft. Hole dry and abandoned. Set bottom plug at 235 ft. and put in 35 sacks of cement. Set top plug at 30 ft. and put in 15 sacks of cement. Put 2 sacks of cement in rat hole. Plugging completed at 8:00 P. M., April 29, 1970. Plugging completed by Hugh Scott, McPherson, Kansas.

TOPS: BROWN LIME - 2578' LANSING - 2633' MISSISSIPPI - 3381'  
KINDERHOOK - 3769' HUNTON - 3820' HAQUOKITA - 3852'  
VIOLA - 3913' SIMPSON - 3932' ARBUCKLE - 4011'



Measurements taken from K. B.

## CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on you J. Roskinson #1, located on the SW SW SW 16-24-38, Harvey County, Kansas as reflected by the files of Blackstone Drilling, Inc.


  
H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas  
on the 30<sup>th</sup> day of April, 1970.


  
Johnnie L. Schmidt - Notary Public


By Commissioner Expires: June 27, 1973.