

DP

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Harvey County, Sec. 18 Twp. 24S Rge. 3 (E) (W) W

Location as "NE/CNW/SW" or footage from lines SW/4 NE/4
Lease Owner O. A. Sutton
Lease Name Devenpeck Well No. 1
Office Address 800 Sutton Place Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed December 20, 19 66
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 19
Plugging completed December 20, 19 66
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Herman Justus, Nickerson, Kansas
Producing formation Depth to top Bottom Total Depth of Well 923 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
1	Sand	0	170			
	Shale	170	205	13 in.	209 ft.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 200 ft. and set plug.
Cemented with 35 sacks. Filled hole to 40 ft. and
set plug. Cemented with 18 sacks cement. Job
Completed at 4:00 A.M., December 20, 1966 by
Herman Justus, Nickerson, Kansas

12-28-66

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Blackstone Drilling, Inc.
Address Box # 455, McPherson, Kansas 67460

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jack G. Paulsen (employee of owner) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.


(Signature) Jack G. Paulsen
800 Sutton Place Bldg., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of December, 19 66

My commission expires June 28, 1970

Jason S Taylor Notary Public.

15-079-30114-0000
BR



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON • KANSAS
67460

December 20, 1966

COMPANY: O. A. SUTTON
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: DEVENPECK # 1
 LOCATION: SW/4 NE/4, Sec. 18-24S-3W,
 Harvey County, Kansas
 COMMENCED: December 8, 1966
 COMPLETED: December 20, 1966
 ELEVATION:

0	to	170	Sand
170	to	205	Shale
205	to	550	Shale & Lime
550	to	830	Lime
830	to	1090	Lime & Shale
1090	to	2010	Shale & Lime
2010	to	2590	Lime & Shale
2590	to	3065	Lime
3065	to	3398	Lime & Shale
3398	to	3609	Mississippi Chert
3609	to	3694	Chert & Lime
3694	to	3757	Lime
3757	to	3801	Kinderhook
3801	to	3820	Hunton Lime
3820	to	3860	Lime
3860	to	3914	Shale
3914	to	3917	Viola
3917	to	3923	Lime
		3923	T. D.

12-28-66
 RECEIVED
 STATE OF KANSAS COMMISSIONER
 DEC 28 1966
 COMMISSIONER ENGINEER
 STATE, KANSAS

Cut 17 1/4 in. hole to 205 ft. and run 209 ft. of 13 in. Surface pipe and cemented with 225 sacks on bottom at 205 ft. Cement circ. with plug at 180 ft. Plug down at 3:00 P.M., December 8, 1966. Cut 7 7/8 in. hole to 3923 ft. Hole Dry and Abandoned. Filled hole with mud to 200 ft. and set plug. Cemented with 35 sacks. Filled hole to 40 ft. and set plug. Cemented with 18 sacks. Job done at 4:00 A.M. and completed by State Plugger, Herman Justus of Nickerson, Kansas on December 20, 1966.

TOPS: Kansas City - 2628' Mississippi - 3398' Kinderhook - 3757'
 Hunton Lime - 3801' Viola - 3914'

Measurements taken from K. B.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Devenpeck #1, located on the SW/4 NE/4 of Sec. 18-24S-3W, Harvey County, Kansas as reflected by the files of Blackstone Drilling, Inc.

H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 20th day of December, 1966.

Ruth McVay - Notary Public

My Commission Expires: December 18, 1969.