

STATE OF KANSAS  
STATE CORPORATION COMMISSION


15-079-0012-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Harvey County, Sec. 22 Twp. 24 Rge. 3 (W)  
Location as "NE/CNW/SW" or footage from lines NE NE NE  
Lease Owner Renfro Drilling Co.  
Lease Name Stutzman Well No. 1  
Office Address 316 Insurance Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 18 19 57  
Application for plugging filed October 18 19 57  
Application for plugging approved October 18 19 57  
Plugging commenced October 18 19 57  
Plugging completed October 18 19 57  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Flat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4086 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with mud from 4086' to 400'.  
Set plug at 400'. Filled with 15 sacks  
cement from 400' to 335'. Filled with  
mud to 20'. Set plug at 20'. Filled  
with 5 sacks cement.

10-24-57

66124  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Renfro Drilling Co.  
Address 316 Insurance Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Henry D. Ficken (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Henry D. Ficken  
316 Insurance Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of October, 19 57

My commission expires May 4, 1959

Jessie  
Notary Public.

PLUGGING  
FILE SEC. 22 T. 24 R. 3W  
BOOK PAGE 56 LINE 10

Operator - Renfro Drilling Co.  
 Well - Stutzman #1  
 Location - NE NE NE Sec. 22-24S-3W  
 Harvey County, Kansas  
 Commenced - October 2, 1957  
 Completed - October 18, 1957  
 Casing - 8-5/8" at 494' with 375 sacks cement  
 Elevation - 1435 Rotary Bushing

DRILLERS LOG

0 - 120	Sand and shale	3411 - 3468	Lime
120 - 375	Shale and lime	3468 - 3510	Lime
375 - 494	Shale and lime	3510 - 3574	Lime and chert
494 - 730	Lime	3574 - 3633	Chert
730 - 760	Shale and red bed	3633 - 3658	Lime
760 - 885	Shale and anhydrite	3658 - 3688	Lime and chert
885 - 1085	Lime	3688 - 3715	Chert
1085 - 1230	Lime	3715 - 3747	Lime
1230 - 1400	Lime and shale	3747 - 3773	Lime
1400 - 1750	Shale, salt & lime	3773 - 3803	Lime
1750 - 2040	Lime and shale	3803 - 3833	Lime
2040 - 2180	Lime and shale	3833 - 3835	Lime
2180 - 2345	Shale and lime	3835 - 3859	Shale
2345 - 2535	Lime and sand	3859 - 3871	Lime
2535 - 2635	Lime	3871 - 3898	Lime and shale
2635 - 2737	Lime	3898 - 3943	Shale and lime
2737 - 2840	Lime	3943 - 3955	Lime
2840 - 2900	Lime	3955 - 3968	Lime
2900 - 2962	Lime	3968 - 3971	Dolomite
2962 - 3030	Lime	3971 - 3976	Sand
3030 - 3090	Lime	3976 - 4013	Shale
3090 - 3164	Lime and shale	4013 - 4045	Sand
3164 - 3253	Lime	4045 - 4060	Sand
3253 - 3300	Lime and shale	4060 - 4072	Lime
3300 - 3320	Lime and shale	4072 - 4086	Lime
3320 - 3371	Shale and lime	4086 -	Total Depth
3371 - 3404	Red bed and sand		
3404 - 3411	Lime		

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers Log is true and correct to the best of my knowledge and belief and according to the records of this office.

RENFRO DRILLING CO.

By

*Henry S. Ficken*

Subscribed and sworn to before me this 23rd day of October, 1957.

*Opaline Lewis*  
 Notary Public

My commission expires May 4, 1959.

10-24-57  
 MED  
 COMMISSION  
 OCT 24 1957  
 CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING  
 FILE SEC 22 T. 24 R. 3W  
 BOOK PAGE 56 LINE 10