

15-069-20214-00-00

KCC OIL/GAS REGULATORY OFFICE

7340 E Colley Ave. Suite 310  
Englewood CO 80111

DATE 9/18/89

[ ] New Situation  
[X] Response to Request  
[ ] Follow-up

OPERATOR Asher Associates Inc. #4868

NAME 5660 Greenwood Plaza Blvd., Suite 206 LOCATION SW NW SW, SEC 20 ,T 26 S,R 29 W

ADDRESS Englewood, CO 80111 LEASE Monger Well # 6

PHONE NO. COUNTY Gray

OPER. 303-770-4100 OTHER

REASON FOR INVESTIGATION: Witness Alternate II cementing.

LEASE INSPECTION

PROBLEM: Need to complete Alternate II cementing.

PERSON(S) CONTACTED: Clint Base of Plains Well Service

FINDINGS: Pumped 1 sx gel and 50 sx 60/40 Pozmix 6% gel and 3% cc, then 50 sx cement 2% cc down tubing. No returns. Pumped 100 sx 60/40 Pozmix with 6% gel and 3% cc down backside. Ran temperature log on 9/19/89.

COMPLAINT

Maximum pump pressure tubing = 600 psi and backside = 100 psi.

RECEIVED  
STATE CORPORATION COMMISSION

Shut in pressure tubing = 300 psi and backside = 100 psi.

Cemented by Allied.

SEP 25 1989  
9-25-89  
CONSERVATION DIVISION  
Wichita, Kansas

photos taken:

ACTION/RECOMMENDATIONS: Ran temperature log on 9/19/89. Alternate II cementing complete. Case closed.

FIELD REPORT

Retain 1 copy Joint District Office  
Send 1 copy Conservation Division

By Michael R. Wilson

9/19/89

