

KCC OIL/GAS REGULATORY OFFICE

15-869-20212-00-00

DATE 9/7/89

[] New Situation
[x] Response to Request
[] Follow-up

OPERATOR Asher Associates Inc. # 4868

NAME 5660 Greenwood Plaza Blvd., Suite 206 LOCATION SW SE SW, SEC 20, T 26 S, R 29 W
& ADDRESS Englewood, CO 80111 LEASE Monger Well # 4

PHONE NO. COUNTY Gray
OPER. 303-770-4100 OTHER

REASON FOR INVESTIGATION: Witness Alternate II cementing.

LEASE INSPECTION

PROBLEM: Need to complete Alternate II cementing.

PERSON(S) CONTACTED: Clint Base of Plains Well Service

FINDINGS: Pumped 2 sx gel, 100 sx ATL, and 50 sx cement with 3% cc down tubing. Pumped 100 sx 60/40 Pozmix 6% gel 2% cc down backside. Ran temperature log.

COMPLAINT

Maximum pump pressure, tubing = 1200 psi, backside = 400 psi.

Shut in pressure, tubing = 400 psi and backside = 200 psi.

Cemented by Allied.

RECEIVED
STATE OF KANSAS
CONSERVATION DIVISION
Topeka, Kansas

SEP 19 1989
9-19-89
CONSERVATION DIVISION
Topeka, Kansas

photos taken:

ACTION/RECOMMENDATIONS: Ran temperature log on 9/8/89. Alternate II completed.

Case closed.

FIELD REPORT

Retain 1 copy Joint District Office
Send 1 copy Conservation Division

By Michael R. Wilson

9/14/89

