

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 22 TWP. 24S RGE. 17W NE
Location as in quarters or footage from lines:
SE SW SE

Locate Well
correctly on above
Section Platt.

Lease Owner Sterling Drilling Company
Lease Name Helen Cross Well No. 3-22
Office Address P. O. Box 129, Sterling, Kansas 67579
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed October 10, 1983
Application for plugging filed October 16, 1983
Plugging commenced 12:30 PM, October 16, 1983
Plugging completed 2:00 PM, October 16, 1983
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bud Metz

Producing formation _____ Depth to top _____ bottom T.D. 4495'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	265'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Filled hole with heavy mud.
Plugged heavy mud through open ended drill pipe
50 sacks at 1130'; 40 sacks at 300'; bridge,
1/2 sack hulls, plug and 10 sacks at 40'; 15 sacks
in rathole. Used 60/40 Pozmix, 2% gel (4% total),
3% cc.

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1983


CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.



STERLING DRILLING COMPANY
(Signature) F. A. Wuellner
P. O. Box 129, Sterling, Kansas 67579
(Address)
F. A. Wuellner, Secretary

SUBSCRIBED AND SWORN TO before me this 17th day of October, 19 83.

Agnes D. Wurst
Agnes D. Wurst, Notary Public.

My Commission expires: 4-6-85

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - HELEN CROSS #3-22
Located: SE SW SE, Section 22-24S-17W, Edwards County, Kansas

OWNER: Sterling Drilling Company
ROTARY DRILLING CONTRACOTR: Sterling Drilling Company

COMMENCED: October 10, 1983
COMPLETED: October 16, 1983

TOTAL DEPTH: 4495'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 130 Surface Soil and Sand	Ran 6 joints new 8 5/8", 24# casing.
130 - 268 Shale	252.81' pipe set at 265' K.B. Cemented
268 - 894 Shale and Sand	with 210 sacks 60/40 Pozmix plus 3% cc.
894 - 1136 Shale and Lime	Plug down at 11:00 AM, 10-19-83, by
1136 - 1149 Anhydrite	Howco.
1149 - 4495 Lime and Shale	Plugged.

Deviation Surveys: 3/4° at 2205'
3/4° at 4372'

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1983

CONSERVATION DIVISION
Wichita, Kansas