

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

Edwards County, Sec. 2 Twp. 24S Rge. (E) 17 (W)  
 Location as "NE/CNW/SW" or footage from lines SE SE SE  
 Lease Owner Chief Drilling, Sunray Mid-Continent, etal.  
 Lease Name Millhouse Well No. 1  
 Office Address P. O. Box 97 - Great Bend, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed November 1 1958  
 Application for plugging filed November 1 1958  
 Application for plugging approved 19  
 Plugging commenced November 1 1958  
 Plugging completed November 1 1958  
 Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot - St. John, Kansas  
 Producing formation Depth to top Bottom Total Depth of Well 4408 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	274'	- 0 -

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set first plug with 1/3 sack hulls and 20 sacks cement @240'.

Set second plug with 1/3 sack hulls and 10 sacks cement @35'.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_  
 Address \_\_\_\_\_

STATE OF KANSAS, COUNTY OF BARTON, ss.  
 V. Richard Hoover (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *V. Richard Hoover*  
 Chief Drilling Co., Inc. - Box 97 - Great Bend, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of November 19 58

My commission expires November 21, 1959

*Mary Johnson*  
 Notary Public.

PLUGGING  
 FILE SEC 2 T 24 R 17W  
 BOOK PAGE 143 LINE 17

11-6-58  
 NOV 6 1958  
 CONSERVATION DIVISION  
 Wichita, Kansas

WELL LOG

Chief Drilling, Sunray Mid-Continent, et al  
 No. 1 Millhouse  
 SE SE SE  
 Section 2-24S-17W  
 Edwards County, Kansas

Date Commenced: October 17, 1958  
 Date Completed: November 1, 1958  
 Casing Record : 270' of 8-5/8" with  
 175 Pozmix, 2% C.C.

Contractor: Chief Drilling Co., Inc.

Elevation : 2092' DF  
 2090' GL  
 2095' KB

Operator : Chief Drilling, Sunray Mid-Continent, et al.  
 P. O. Box 97 - Great Bend, Kansas

D. & A.

Formation	From	To	Formation Tops and Tests	Welex Electric Log Tops
Surface Soil, Clay, Sand	0	50		
Sand, Shale & Shells	50	270		
Shale & Shells	270	395	Heebner 3693 (-1598)	
Shale & Red Bed	395	600	Brown Lime 3818 (-1723)	
Sand	600	660	Lansing 3826 (-1731)	
Shale & Shells	660	1103	Cherokee Sand 4245 (-2150)	4255 (-2160)
Anhydrite	1103	1125	Mississippi 4269 (-2174)	4270 (-2125)
Shale & Shells	1125	1900	Kinderhook Sand 4322 (-2227)	4332 (-2237)
Shale & Lime	1900	2055	Viola 4366 (-2271)	
Lime	2055	2170	Total Depth 4408 (-2313)	
Lime & Shale	2170	2765		
Fron, Shale & Shells	2765	2880		
Shale & Shells	2880	3485	Drill Stem Test #1:	
Lime & Shale	3485	3765	Depth: 4271-4280. Tool open 1 hour; shut in 30 minutes. Good blow throughout.	
Lime	3765	4230	Rec: 25' slightly gas cut mud, no shows.	
Lime & Shale	4230	4269	IFF 28#. FFP 32#. IBHP 1015#/30.	
Chert	4269	4280	FBHP 47#/30.	
Mississippi	4280	4297	Drill Stem Test #2:	
Chert	4297	4312	Depth: 4280-4297. Tool open 1 hour.	
Lime	4312	4408	Blow: Good throughout.	
Total Depth		4408	Rec: 43' slightly gas cut mud with slight scum of oil.	
			IFF 40#. IBHP 1410#/20. FBHP 264#/30.	

STATE OF KANSAS )  
 ) SS.  
 COUNTY OF BARTON )

I hereby certify that the above is a true and correct copy of Driller's Log of the well drilled in the SE SE SE of Section 2-24S-17W, Edwards County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*V. Richard Hoover*  
 V. Richard Hoover, President

Subscribed and sworn to before me this 4th day of November, 1958.

*Mary C. Johnson*  
 Notary Public

My Commission Expires: November 21, 1959

11-6-58  
 RECEIVED  
 STATE OF KANSAS COMMISSIONER

NOV 6 1958

CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING  
 FILE SEC 2 T 24 R 17W  
 BOOK PAGE 143 LINE 17