

To be filed with State Corp. Comm.

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

15-047-21129-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 2 TWP. 24S RGE. 17W ~~SW~~W
Location as in quarters or footage from lines:
SW SW NE

Lease Owner F. G. Holl
Lease Name Twitchell Well No. 2-2
Office Address 6427 East Kellogg, Wichita, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed November 13, 1983
Application for plugging filed November 13, 1983
Plugging commenced 3:15 PM November 13, 1983
Plugging completed 4:45 PM November 13, 1983
Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clyde Wiley

Producing formation _____ Depth to top _____ bottom T.D.4495'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	257'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Filled hole with heavy mud.
Plugged through open ended drill pipe 50 sacks
at 720'; 50 sacks at 355'; solid bridge, 1/2 sack
hulls, plug and 10 sacks at 40'. 15 sacks in
rathole. Did not plug water well. Used 60/40
Pozmix plus 2% gel (total 4%); plus 3% cc.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
(Address) P. O. Box 129, Sterling, Ks 67579

SUBSCRIBED AND SWORN TO before me this 14th day of November, 1983.



Agnes D. Wurst
Agnes D. Wurst, Notary Public.

RECEIVED 11-18-83
STATE CORPORATION COMMISSION
NOV 18 1983
CONSERVATION DIVISION
Wichita, Kansas

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - TWITCHELL #2-2

Located: SW SW NE, Section 2-24S-17W, Edwards County,

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 7, 1983

COMPLETED: November 13, 1983

TOTAL DEPTH: 4495'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 6 joints new 8 5/8", 24# casing. 244.69' pipe set at 257' K.B.
90 - 260 Shale and Clay	Cemented with 210 sacks 60/40 Pozmix plus 3% cc. Plug down at 11:45 AM, 11-7-83, by Howco.
260 - 770 Shale and Sand	
770 - 1110 Shale	
1110 - 1129 Anhydrite	
1129 - 4495 Lime and Shale	Plugged.

Deviation Surveys: 1° at 2150'
3/4° at 4360'

11-18-83

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1983

CONSERVATION DIVISION
Wichita, Kansas