

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
206 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21,284-0000

LEASE NAME Massey "C"

WELL NUMBER 2-2

4950' Ft. from S Section Line

4620' Ft. from E Section Line

SEC. 2 TWP. 24 SRGE. 17 ~~W~~ W

COUNTY Edwards

Date Well Completed 5-18-87

Plugging Commenced 8:30 AM, 5-18-87

Plugging Completed 12:30 PM, 5-18-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F. G. Holl Estate

ADDRESS P. O. Box 780167  
Wichita, Kansas 67278-0167

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D&A

(Oil, Gas, D&A SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? District No. 1

Is ACO-1 filed?                      If not, is well log attached? Yes

Producing Formation                      Depth to Top                      Bottom                      T.D.                     

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	309'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set.

Filled hole with heavy mud. 50 sacks 60/40 Pozmix, 6% gel at 1141';  
50 sacks at 335'; 10 sacks 0 to '40'. 15 sacks in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129  
Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *F. A. Wuellner*

(Address) F. A. Wuellner, Secretary  
P. O. Box 129, Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 19th day of May, 19 87.

RECEIVED  
STATE CORPORATION COMMISSION  
Agnes D. Wurst, Notary Public

My Commission Expires: 4-6-89

*Reed 5-25-87*

# STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - MASSEY "C" #2-2

Located: C N/2 NW NW, Section 2-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl Estate

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 12, 1987

COMPLETED: May 18, 1987

TOTAL DEPTH: 4450'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soils and Sand	Ran 7 joints 8 5/8" casing. 299.03'
90 - 260 Clay and Shale	pipe set at 309' K.B. Cemented with
260 - 311 Shale	225 sacks 60/40 Pozmix, 2% gel and
311 - 1115 Shale, Sand, Red Bed	3% cc. Plug down at 5:15 PM, 5-12-87,
1115 - 1120 Shale	by Howco.
1120 - 1141 Anhydrite	
1141 - 1975 Shale and Lime Stringers	
1975 - 4450 Lime and Shale	Plugged.

Deviation Surveys: 3/4° at 2145'  
1 3/4° at 4277'

RECEIVED  
STATE CORPORATION COMMISSION

MAY 25 1987

CONSERVATION DIVISION  
Wichita, Kansas

*Reed*  
*5-25-87*