

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15 - 047 - 21,288
 LEASE NAME Massey

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 4-2

1155' Ft. from S Section Line

4950' Ft. from E Section Line

SEC. 2 TWP. 24 SRGE. 17 (E) (W)

COUNTY Edwards

Date Well Completed 9-14-87

Plugging Commenced 9:15 PM, 9-14-87

Plugging Completed 10:00 PM, 9-14-87

LEASE OPERATOR F. G. Holl Company
 ADDRESS 6427 East Kellogg
Wichita, Kansas 67207

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? District No. 1

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	321.46'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud. Heavy mud to 1155' with 50 sack plug at 1155'
through open ended drill pipe, with 40 sack plug at 500' and 40 sack plug at 360',
with 10 sack at 40' to surface. 15 sacks in rathole. Used 60/40 Pozmix with 8% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129
Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

Richard L. Mead (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Richard L. Mead
 (Address) P. O. Box 129, Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 15th day of September, 19 87

Agnes D. Wurst
 Notary Public

My Commission Expires: April 6, 1989

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 17 1987
9-17-87
 CONSERVATION DIVISION
 Wichita, Kansas
 Form CP-4
 Revised 07-86

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - MASSEY #4-2

Located: N/2 NW SW SW, Section 2-24S-17W, Edwards County,
Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 8, 1987.

COMPLETED: September 14, 1987

TOTAL DEPTH: 4434'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 75 Sand	Ran 8 joints 8 5/8", 23# new casing.
75 - 120 Clay, Shale	321.46' pipe set at 333.00 K.B.
120 - 1132 Shale	Cemented with 225 sacks 60/40 Pozmix, with 2% gel and 3% cc. Plug down at 10:30 PM, 9-8-87, by B. J. Titan.
1132 - 1154 Anhydrite	
1154 - 1490 Shale, Lime Stringers	
1490 - 4434 Lime and Shale	Plugged.

9-17-87

Deviation Surveys:

RECEIVED 2045'
11/4° E 4434'
STATE CORPORATION COMMISSION

SEP 17 1987

CONSERVATION DIVISION
Wichita, Kansas