

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-20,988
LEASE NAME MASSEY 0000
WELL NUMBER C1-2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. HOLL CO.

ADDRESS 6427 E. KELLOGG WICHITA, KS.

PHONE#(316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-9-1993 (date)

by DUANE RANKIN (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation _____ Depth PBTD to Top 4396 Bottom _____ T.D. 4420

Show depth and thickness of all water, oil and gas formations. PERFS. 4362-66 PLUG AT 4263-68 4330

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	250	8 5/8	250	0
		0	4414	4 1/2	4414	2300 - 54 JTS.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

8-6-93: DUMPED SAND + CEMENT (4 SK). TOP OF SAND AT 4080 FT.
8-9-93: SHOT OFF CSG. AT 2300 FT - PULLED 54 JTS.
8-10-93: ALLIED TOP HOLE PLUGGED WITH 300# HULLS - 10 SK GEL, 50 SK CEMENT, 10 SK GEL, 100# HULLS, 8 5/8 PLUG - 150 SK CEMENT. 60-40 + 6%.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893


Address PO Box 847 PRATT, KS. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F. G. HOLL CO.

STATE OF KANSAS COUNTY OF PRATT, ss. 8-25-93

JUDY BERRY (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed with the STATE CORPORATION COMMISSION and the same are true and correct, so help me God.

(Signature) Judy Berry
(Address) 90 PWS, Inc AUG 25 1993



SUBSCRIBED AND SWORN TO before me this 23RD day of August 1993

Dorothy M. Furgason Notary Public

My Commission Expires February 6, 1997

15-047-20988-0000

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 14 1993

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

CONSERVATION DIVISION
WICHITA, KS

WELL LOG - - - - - MASSEY "C" #1-2
Located: 330' FNL; 1320' FWL, NW/4, Section 2-24S-17W,
Edwards County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 3, 1982
COMPLETED: January 9, 1982

TOTAL DEPTH: 4420'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 105 Sand	Ran 6 joints new 8 5/8", 24# casing.
105 - 253 Shale	237.97' pipe set at 250' K.B. Cemented
253 - 1123 Shale, Sand and Red Beds	with 210 sacks 60/40 Pozmix with 3% cc.
1123 - 1138 Anhydrite	Plug down at 5:45 PM, 1-3-82, by Howco.
1138 - 1920 Shale and Lime Stringers	
1920 - 4420 Lime and Shale	Ran 107 joints new 4 1/2", 10.5# OD
	casing. 5 joints have been sandblasted.
	4405.49' pipe set at 4414' K.B. Cemented
	with 100 sacks Lite and 125 sacks 50/50
	Pozmix plug regular additives. Plug
	down at 8:50 AM, 1-9-82, by Howco.

Deviation Surveys: 1° at 2256'
1 3/4° at 4330'