

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-20,682-  
LEASE NAME Twitchell #1-2  
WELL NUMBER \_\_\_\_\_

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

SPOT LOCATION NE NE NE  
SEC. 2 TWP. 24s RGE. 17W or (W)

LEASE OPERATOR F.G. Holl  
ADDRESS 6427 E. Kellogg, Wichita, Kansas 67207

COUNTY Edwards  
Date Well Completed \_\_\_\_\_

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Plugging Commenced 10/1/85

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10/28/85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4360'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	278'	none
				4 1/2"	4359'	2118'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 4200' & 4 sacks cement. Shot pipe at 3028', 2814', 2619', 2407', 2213', 2118'. Pulled 53 joints of pipe. Plugged well with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, 8 5/8 plug, & 150 sacks 60/40 poz 6% gel.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 29th day of October, 1985

My Commission expires:



Irene Hoover  
Notary Public  
STATE CORPORATION COMMISSION

10-31-85  
OCT 31 1985

Form CP-4  
Revised 01-84

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- TWITCHELL #1-2  
Located: NE NE NE, Section 2-24S-17W, Edwards County,  
Kansas

OWNER: F. G. Holl  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 19, 1980  
COMPLETED: May 26, 1980

TOTAL DEPTH: 4360'

<u>LOG</u>		<u>CASING RECORD</u>
0 - 80	Surface Soil and Sand	Ran 6 joints new 280, 8 5/8" casing, 266' set at 278' K.B. Cemented with 225 sacks 60/40 Pozmix with 3% cc. Plug down at 10:15 PM, 5-19-80, by Howco.
80 - 281	Shale, Sand, Red Bed	
281 - 1095	Red Beds and Shale	
1095 - 1109	Anhydrite	
1109 - 1447	Shale	
1447 - 2110	Shale, Lime and Salt	
2110 - 4145	Lime and Shale	
4145 - 4317	Lime	Ran 7 joints used and 110 joints new 10.50 4 1/2" OD casing. 4349.92' set at 4359' K.B. Cemented with 17t sacks Regular Mix. Plug down at 7:45 AM, 5-26-80, by Howco.
4317 - 4360	Sand, Shale and Lime	

Deviation Surveys: 1 1/2° at 2150'  
3/4° at 4288'

8-20-85  
AUG 20 1985