


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County, Sec. 6 Twp. 24S Rge. 17W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____



Locate well correctly on above Section Plot

C SW
Lease Owner F. G. Holl
Lease Name Hoar #1 Well No. 1
Office Address 6427 East Kellogg, Wichiat, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole) _____

Dry Hole
Date Well completed November 12, 1977 19
Application for plugging filed November 12, 1977 19
Application for plugging approved November 12, 1977 19
Plugging commenced 11:45 AM, November 12, 1977 19
Plugging completed 12:45 PM, November 12, 1977 19
Reason for abandonment of well or producing formation _____

Dry Hole
If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4755'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	256'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
Pumped thru open ended D.P.
40 sacks @ 500' and 35 sacks @ 240'.
Solid Bridge with hulls and plug @ 40' with
12 sacks to surface. 2 sacks in rathole.
Used 50/50 Pozmix.

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1977
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor STERLING DRILLING COMPANY, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
E. A. Wuellner (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


STERLING DRILLING COMPANY
(Signature) E. A. Wuellner
E. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of November, 19 77

CHARLES HALL—NOTARY PUBLIC
My Commission Expires Jan. 6, 1978

Charles M. Hall
Charles M. Hall, Notary Public.

My commission expires _____



STERLING DRILLING COMPANY
 P. O. Box 129
 Sterling, Kansas 67579

WELL LOG ----- HOAR #1
 Located: C-SW, Section 6-248-17N, Edwards County, Kansas

OWNER: F. G. Holl
 ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 3, 1977
 COMPLETED: November 12, 1977

TOTAL DEPTH: 4755'

LOG

CASING RECORD

0 - 70 Sand and Clay
 70 - 160 Shale and Sand, Red Bed
 160 - 259 Red Bed and Shale
 259 - 1100 Shale, Sand and Red Bed
 1100 - 1182 Red Bed
 1182 - 1201 Anhydrite
 1201 - 1915 Shale, Shells and Salt
 1915 - 2080 Shale and Lime Stg.
 2080 - 4015 Shale and Lime
 4015 - 4225 Lime
 4225 - 4377 Lime and Shale
 4377 - 4385 Cherty, Sahly, Lime
 4385 - 4413 Chert and Lime, Shale
 4413 - 4425 Cherty Lime and Shale
 4425 - 4500 Chert, Sand, Lime and Shale
 4500 - 4550 Chert and Cherty, Lime and Shale
 4550 - 4625 Cherty Lime and Shale
 4625 - 4680 Lime, Chert and Shale
 4680 - 4750 Cherty Lime and Shale
 4750 - 4755 Ar buckle

Ran 6 joints used 287, 8 5/8" casing,
 244.98' set at 256' K.B. with 225
 sacks 60/40 Pozmix with 33 cc. Plug
 down at 5:30 PM, 11-3-77, by Howco.

RECEIVED
 STATE CORPORATION COMMISSION

NOV 29 1977

CONSERVATION DIVISION
 Wichita, Kansas

Plugged.