

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 7 TWP. 24S RGE. 17 W/W
Location as in quarters or footage from lines:
C NW NW

Locate Well
correctly on above
Section Platt.

Lease Owner F. G. Holl
Lease Name Sowers-Allen Well No. 1-7
Office Address 6427 East Kellogg, Wichita, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed December 8, 1983
Application for plugging filed December 8, 1983
Plugging commenced 11:00 AM, December 8, 1983
Plugging completed 12:30 PM, December 8, 1983
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bud Metz

Producing formation _____ Depth to top _____ bottom _____ T.D. 4560'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	258'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Filled hole with heavy mud.
Plugged through open ended drill pipe 50 sacks
at 1180'; 60 sacks at 300'; 1/2 sack hulls,
plug and 10 sacks at 40'. 15 sacks in rathole
and 5 sacks in water well. Used 60/40 Pozmix,
2% gel (total 4%) and 3% cc.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY

(Signature) F. A. Wuellner

F. A. Wuellner, Secretary

(Address)

P. O. Box 129, Sterling, Ks 67579

SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 83.



Agnes D. Wurst
Agnes D. Wurst, Notary Public.

My Commission expires: 4-6-85

RECEIVED
STATE CORPORATION COMMISSION

DEC 13 1983

12-13-83

15-047-21136-0000

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - SOWERS-ALLEN #1-7
Located: c nw nw, Section 7-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: December 2, 1983

COMPLETED: December 8, 1983

TOTAL DEPTH: 4560'

<u>LOG</u>		<u>CASING RECORD</u>	
0 - 90	Surface Soil and Sand	Ran 6 joints new 8 5/8", 24# casing. 244.71' pipe set at 258' K.B. Cemented with 200 sacks 60/40 Pozmix, 3% cc. Plug down at 1:30 PM, 12-2-83, by Howco.	
90 - 260	Shale		
260 - 490	Shale and Red Bed		
490 - 1180	Shale and Lime		
1180 - 1194	Anhydrite		
1194 - 1280	Shale and Lime		
1280 - 2000	Shale and Lime Str.		
2000 - 4432	Lime and Shale		
4432 - 4450	Chert		
4450 - 4560	Chert, Shale, Lime		Plugged.

12-13-83

Deviation Surveys: 1 3/4° at 2264'
1° at 4432'

RECEIVED
STATE CORPORATION COMMISSION

DEC 13 1983

CONSERVATION DIVISION
Wichita, Kansas