

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15 - 047-21,309-  
0000  
LEASE NAME Leon Smith #7-10  
WELL NUMBER #7-10  
4950 Ft. from S Section Line  
990 Ft. from E Section Line  
SEC. 10 TWP. 24S RGE. 17W (E) (W)  
COUNTY Edwards

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F. G. Holl Company  
ADDRESS P. O. Box 780167  
Wichita, Kansas 67278-0167  
PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Date Well Completed March 19, 1988  
Plugging Commenced 9:00 PM, 3-19-88  
Plugging Completed 10:30 PM, 3-19-88

Character of Well D & A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 19, 1988 (date)  
by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	322' K.B.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Filled hole with heavy mud; 50 sacks at 1150'; 40 sacks at 560'; 50 sacks at 360';  
10 sacks 0 to 40'. 15 sacks in rathole. Used 60/40 Pozmix with 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142  
P. O. Box 129  
Address Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (Employee of Operator) or (Operator) of  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,  
statements, and matters herein contained and the log of the above-described well as filed that  
the same are true and correct, so help me God.

(Signature) F. A. Wuellner  
(Address) F. A. Wuellner, Secretary  
P. O. Box 129, Sterling, KS 67579

SUBSCRIBED AND SWORN TO before me this 21st day of March, 19 88

Agnes D. Wurst  
Agnes D. Wurst, Notary Public  
4-6-89

My Commission Expires:



## STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- LEON SMITH #7-10  
 Located: NW NE NE, Section 10-24S-17W, Edwards County,  
 Kansas

OWNER: F. G. Holl Company  
 ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: March 14, 1988  
 COMPLETED: March 19, 1988

TOTAL DEPTH: 4480'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 92 Sand	Ran 7 joints 8 5/8" casing. 308.45' pipe set at 322' K.B. Cemented with 225 sacks 60/40 Pozmix, 2% gel and 3% cc. Plug down at 1:45 PM, 3-14-88, by B. J. Titan.
92 - 370 Red Beds	
370 - 1111 Shale, Red Beds	
1111 - 1124 Anhydrite	
1124 - 1370 Shale	
1370 - 4480 Lime and Shale	Plugged.

Deviation Surveys: 3/4° at 2185'  
 1° at 4318'

RECEIVED  
 STATE CORPORATION COMMISSION  
 3-23-88  
 MAR 23 1988

CONSERVATION DIVISION  
 Wichita, Kansas