

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-21,212-

LEASE NAME Leon Smith 4-10

WELL NUMBER

SPOT LOCATION NE NE NE

SEC. 10 TWP. 24S RGE. 17W or (W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 8/28/85

Plugging Completed 10/28/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F.G. Holl

ADDRESS 6427 E. Kellogg, Wichita, Ks. 67207

PHONE #(316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? If not, is well log attached?

Producing formation Depth to top bottom T.D. 4495'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	258'	none
				4 1/2"	4489'	2656'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 4270' & 4 sacks cement. Shot pipe at 3512', 3217', 3017', 2912', 2818', 2705', & 2656'. Pulled 66 joints of pipe. Plugged well with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, 8 5/8 plug, & 150 sacks 60/40 poz 6% gel.
Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 29th day of October, 1985

REC'D
STATE CORPORATION COMMISSIONARY PUBLIC

My Commission expires:



OCT 31 1985 10-31-85

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - LEON SMITH #4-10
Located: NE NE NE, Section 10-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 8, 1984

COMPLETED: October 16, 1984

TOTAL DEPTH: 4495'

LOG

CASING RECORD

0 - 90 Surface Soil and Sand
 90 - 261 Shale and Sand
 261 - 1112 Shale, Sand, Red Beds
 1112 - 4475 Lime and Shale
 4475 - 4495 Lime

Ran 6 joints new 8 5/8", 23# casing.
 246.26' pipe set at 258' K.B.
 Cemented with 210 sacks 60/40 Pozmix plus
 3% cc. Plug down at 12:00 PM, 10-8-84,
 by Howco.

Ran 111 joints 4 1/2", 10.5# casing.
 11 joints were used. 4479.99' pipe
 set at 4489 K.B. Cemented with 100
 sacks Lite and 125 sacks 50/50 Pozmix,
 plus our regular additives. Plug
 down at 8:30 PM, 10-16-84, by Howco.
 Plugged rathole and water well will
 be plugged.

Deviation Surveys: 1° at 2182'
1° at 4354'

RECEIVED
STATE CORPORATION COMMISSION

JUN 18 1985 6-18-85

CONSERVATION DIVISION
Wichita, Kansas