

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-20,639-0000

LEASE NAME Boyd

WELL NUMBER #2-10

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 10 TWP. 24 SRGE. 17 W COR (W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 3/15/89

Plugging Completed 3/29/89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F.G. Holl Company

ADDRESS Box 158
Belpre, KS

PHONE# (316) 995-3171 OPERATORS LICENSE NO. 5056

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4455'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	269	none
				4 1/2	4453	2250

4-5-89 RECEIVED
STATE CORPORATION COMMISSION
5 1989
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged bottom with sand to 4270', ran 4 sacks cement, shot @2478',
2394', 2250', plugged surface with 400# hulls, 10 gel, 50 sacks cement,
10 gel, 100# hulls, 8 5/8" plug, 120 sacks 60/40 poz 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address * P.O. Box 347 Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 3rd day of April, 19 89

My Commission Expires:



James Hoover
Notary Public

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - BOYD #2-10
Located: 440' FNL; 400' FWL, SW/4, Section 10-24S-17W,
Edwards County, Kansas

OWNER: T. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: March 21, 1980
COMPLETED: March 27, 1980

TOTAL DEPTH: 4455'

LOG

CASING RECORD

- 0 - 85 Surface Soil and Sand
- 85 - 272 Sand, Clay
- 272 - 390 Shale, Sand, Red Beds
- 390 - 1140 Red Bed, Shale
- 1140 - 1165 Anhydrite
- 1165 - 1700 Shale and Shells
- 1700 - 3840 Lime and Shale
- 3840 - 4220 Lime, Shale and Chert
- 4220 - 4367 Lime and Shale
- 4367 - 4420 Lime and Chert
- 4420 - 4455 Lime

Ran 7 joints used 280, 8 5/8" casing.
257.17' set at 269' K.B. Cemented with
225 sacks 60/40 Pozmix with 3% cc. Plug
down at 8:30 PM, 3-21-80, by Howco.

RECEIVED
STATE CORPORATION COMMISSION

FEB 23 1989 2-23-89

CONSERVATION DIVISION
Wichita, Kansas

Ran 103 joints 4 1/2" OD new 10.5# casing.
4443.72' set at 4453' K.B. Cemented with
175 sacks Regular Mix. Plug down at
10:45 PM, 3-27-80, by Howco.

Deviation Surveys: 1° at 2196'
3/4° at 4367'