

15-047-20330-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A

LEASE NAME L. Smith

WELL NUMBER 1-10

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 10 TWP. 24 RGE. 17W *E) or (W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 11/14/89

Plugging Completed 11/21/89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. Holl Company

ADDRESS P.O. Box 158 Belpre, KS. 67519

PHONE#(316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4394'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	240	none
				4 1/2	4439	2411

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom to 4280'. Dumped 4 sacks cement. Shot pipe @3020', 2621' and 2411'. Plugged with 4 hulls, 10 gel, 50 sacks cement, 10 gel, 1 hull, 125 sacks 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 30 day of November, 19 89

[Signature]
Notary Public

My Commission Expires:



RECEIVED
STATE CORPORATION COMMISSION

DEC - 5 1989

15-047-20330-0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- WITNESS #1
located: 390' WBL, 399' FSL, NW/4, Section 10-24S-17,
Edwards County, Kansas

OWNER: F. C. Holl, et al
CONTACT DRILLING CONTRACTOR: Sterling Drilling Company

COMPLETION: January 30, 1978
COMPLETION: February 8, 1978

TOTAL DEPTH: 4440'

LOG

CASING RECORD

0 - 185 Sand and Clay
185 - 243 shale
243 - 560 shale and sand
560 - 1141 Red Bed
1141 - 1159 Anhydrite
1159 - 1355 shale
1355 - 1785 shale and salt
1785 - 3758 shale and lime
3758 - 3850 shale
3860 - 4065 lime
4065 - 4328 lime and shale
4328 - 4370 Cherty
4370 - 4405 lime, shale and sand
4405 - 4435 lime and shale
4435 - 4440 Cherty lime

Ran 6 joints used 2 1/2", 8 5/8" casing, 225.18'
set at 240' P. P. with 225 sacks G/40 Pozmix
with 3% cc. Plug down at 12:30 AM, 1-31-78,
by Howco.

AUG 23 1989

CONSERVATION DISTRICT
WICHITA, KANSAS

Ran 137 joints new 10.5", 4 1/2" casing,
4431.6' set at 4439' K.P. with 50 sacks Howco
light and 100 sacks Pozmix with 10% salt and
5" Gilsonite and 3/4" GFR2 and 1/8" Floceal
and 1/8" Tuffiber per sack. Plug down at
11:15 PM, 2-8-78, by Howco.