

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 10 TWP. 24S RGE. 17W E/W
Location as in quarters or footage from lines:
900' N of C of SL

Locate Well
correctly on above
Section Platt.

Lease Owner E.G. Holl
Lease Name Boyd Well No. 1-10
Office Address 6427 East Kellogg Wichita, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 8-17-81
Plugging completed 8-20-81
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation _____ Depth to top _____ bottom _____ T.D. 4420'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	285	none
				4-1/2"	4409	2351'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

~~Moved in on location, ran sand to 4250' and set 4 sacks cement, pulled 18-3/4" tension.
Shot Pipe @3505', 3015', 2825', 2435' & 2340'. Pulled 74 joints pipe. Plugged well
with 15 sacks gel, 6 sacks hulls, 10 sacks gel, 125 sacks 50/50 pos, 4% gel, 3% cc.
Plugging completed.~~

8-27-81

RECEIVED
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

CONSERVATION DIVISION
Wichita, Kansas

(Signature) R. Darrell Kelso
R. Darrell Kelso
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of August, 19 81

My Commission expires:



Irene Hoover
Notary Public.