

15-047-00283-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Edwards County. Sec. 10 Twp. 24 Rge. 17 (E)W (W)

Location as "NE/CNW&SW&" or footage from lines C NE NW

Lease Owner G. H. Spoor, Jr.

Lease Name Wilcox Well No. 1

Office Address 1078 Armour Lane

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed January 9, 19 63

Application for plugging filed January 9, 19 63

Application for plugging approved January 9, 19 63

Plugging commenced January 9, 19 63


Plugging completed January 9, 19 63

Reason for abandonment of well or producing formation No oil and/or gas found in commercial quantities.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. R. Lac Kamp

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	244'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 240'.

Set plug #1 and 20 sx cement.

Filled hole with extra heavy rotary mud from plug #1 to 40'.

Set plug #2 at 40' and 10 sacks cement.

1-15-63

STATE CORPORATION COMMISSION

JAN 15 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company

Address 814 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. R. McNicol

814 Union Center, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of January 19 63

Meri Rose Shenk Notary Public.

My commission expires October 18, 1966



ROTARY DRILLING LOG

OWNER: C. H. Spoor, Jr.  
CONTRACTOR: Prime Drilling Company  
LEASE: Wilcox #1  
LOCATION: C NE NW Sec. 10-24-17W  
Edwards County, Kansas

CASING: Set 8 5/8" @ 244' 225' sx  
HAS. Poz

0-110	Sand
110-400	Shale
400-840	Red Bed
840-1125	Red Bed & Shale
1125-1155	Anhy
1155-1450	Shale & Shells
1450-1670	Lime & Shale
1670-2180	Shale & Lime
2180-2375	Lime
2375-2475	Lime & Shale
2475-2655	Shale & Lime
2655-2775	Lime
2775-3285	Shale & Lime
3285-3505	Shale
3505-3718	Lime & Shale
3718-3810	Shale & Lime
3810-4298	Lime
4298-4310	Lime & Chert
4310-4328	Miss Lime
4328-4335	Kind. Shale
4335-4370	Shale, Lime & Chert
4370-4418	Lime & Shale
4418	Rotary Total Depth

1-15-63  
JAN 15 1963

CONSERVATION ENGINEER  
Wichita, Kansas

We certify that the above log is true and correct to the best of our knowledge and belief.

PRIME DRILLING COMPANY

BY R. R. McNicol  
R. R. McNicol