


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Edwards County. Sec. 10 Twp. 24S Rge. 17W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
SW SW NE,  
Lease Owner F. G. Holl  
Lease Name Leon Smith #2-10 Well No. #2-10  
Office Address 6427 East Kellogg, Wichita, Kansas 67207  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plot

Dry Hole  
Date Well completed March 12, 1981 19  
Application for plugging filed March 12, 1981 19  
Application for plugging approved March 12, 1981 19  
Plugging commenced 7:00 AM, March 12, 1981 19  
Plugging completed 9:15 AM, March 12, 1981 19  
Reason for abandonment of well or producing formation

Dry Hole  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie  
Producing formation Depth to top Bottom Total Depth of Well 4420'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	288'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Filled hole with heavy mud.  
Heavy mud to 540' with 40 sacks through open ended  
drill pipe. Heavy mud to 275' with 30 sacks through  
open ended drill pipe. Heavy mud to 40; with Howco  
plug and 1/2 sack hulls, solid bridge at 40' with 10  
sacks to surface, 10 sacks in rathole. Used 50/50 Pozmix.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.  
F. A. Wuellner (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner  
STERLING DRILLING COMPANY  
F. A. Wuellner, Secretary  
P. O. Box 129, Sterling, Kansas 67579  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of March, 1981.

My commission expires



Charles M. Hall  
Charles M. Hall, Notary Public

APR - 1 1981  
4-1-81  
Conservation Division  
Wichita, Kansas

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG - - - - - LEON SMITH #2-10  
Located: SW SW NE, Section 10-24S-17W, Edwards County,  
Kansas

OWNER: F. G. Holl  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: March 6, 1981  
COMPLETED: March 12, 1981

TOTAL DEPTH: 4420'

LOG

0 - 95 Sand  
95 - 292 Clay and Shale  
292 - 1116 Shale, Sand, Red Beds  
1116 - 1132 Anhydrite  
1132 - 1919 Shales  
1919 - 4420 Lime and Shale

CASING RECORD

Ran 7 joints used 8 5/8", 24# casing.  
276.61' set at 288' K.B. Cemented  
with 225 sacks 60/40 Pozmix with 3% cc.  
Plug down at 4:00 PM, 3-6-81, by Howco.

Plugged.

Deviation Surveys: 3/4° at 1919'  
1/4° at 4332'