

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas. 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-047-00243-0001

API NUMBER _____ OWWO _____
LEASE NAME _____ BRITTON _____
WELL NUMBER _____ 2-15 _____

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. HOLL ESTATE
ADDRESS 6427 East Kellogg, Wichita, KS 67207

PHONE#(316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Mississippian Depth to Top 4300 Bottom 4340
Arbuckle 4670 T.D. 4962

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippi	Gas & Oil	4300	4340	16"	97'9"	None
Arbuckle	Water	4670	4962	10 3/4"	1064'0"	None
				5 1/2"	4765'0"	1491'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

* See Attachment

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor _____ License No. _____

Operator plugged according to state regulations

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Elwyn H. Nagel

(Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

STATE CORPORATION COMMISSION


(Signature) Elwyn H. Nagel
Elwyn H. Nagel, Manager
(Address) 6427 E. Kellogg, Wichita, Ks. 67207

4-23-86

APR 23 1986

SUBSCRIBED AND SWORN to before me this 21st day of April, 1986

Wichita, Kansas



(Signature) Mary D. Slagle
Notary Public

Expires: _____

Britton A2-15 SWD
4-7-86

Ran 90 joints 2" tubing set at 2800'.
Rigged up Halliburton to squeeze well.
Mixed and pumped 250 sacks 50/50 poz
mix with 6% Halad 9 water loss and 2%
gel and 250 sacks 50/50 poz with 2%
gel at 4 bpmp 100#. Cement in, shut
down, on vacuum. Still on vacuum
taking $\frac{1}{2}$ bpm after 45 minutes.
Pumped 15 barrels water down tubing
to clean. Mixed 50 sacks cement with
2% calcium chloride and 3 sacks hulls.
Pumped 11 barrels. Pulled 20 joints
tubing. Waited 2 hours and ran
measuring line. Could not get below
2000'. Pulled rest of tubing. Ran
line down casing. TOC at 2100'.
Will pull casing in a.m.
Cost: \$5,641.13

Britton A2-15 SWD
4-8-86

Went in to shoot 5 $\frac{1}{2}$ " casing. Found
TD at 1500'. Came up to collar at
1491' and shot off. Pulled 38 joints
5 $\frac{1}{2}$ " casing. Broke off braden head.
Rigged down and moved off.

Britton A2-15 SWD
4-10-86

Halliburton PTA well with 4 sacks hulls
and 200 sacks 35% poz, 65% common,
10% gel, 2% econolite 2 bpm 500#.
Closed in. Plugged to state
recommendations.
Cost: \$2,475.44
Total cost of plugging well: \$10,969.07

4-23-86
RECEIVED
STATE CORPORATION COMMISSION

APR 23 1986

CONSERVATION DIVISION
Wichita, Kansas