

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Edwards County, Sec. 14 Twp. 24 Rge. (E) 17(W)

Location as "NE/CNW/SW" or footage from lines C NE SE

Lease Owner DONALD C. SLAWSON

Lease Name Fertig 'A' Well No. 1

Office Address 408 One Twenty Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-17-65

Application for plugging filed 10-17-65

Application for plugging approved 10-20-65


Plugging commenced 10-17-65

Plugging completed 10-17-65

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well A. Elving, Box 248, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4435 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 275', set plug, 1/4 sack hulls,
25 sacks regular cement, mud to 40',
set plug, 1/4 sack hulls, 10 sacks regular
cement, 2 sacks regular cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION
11-4-65
NOV 4 1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.
Address 408 One Twenty Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

DONALD C. SLAWSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
408 One Twenty Building, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of November, 19 65

My commission expires August 25, 1968 Ella Priess Notary Public.

WELL LOG

Company: DONALD C. SLAWSON
 408 One Twenty Building
 Wichita, Kansas

Farm: Fertig 'A' #1
 C NE SE, Section 14-24-17W
 Edwards County, Kansas

Total Depth: 4435' Elev. 2104 K.B.

Commenced: October 7, 1965
 Completed: October 17, 1965

Contractor: Slawson Drilling Company, Inc.

Casing: 8 5/8" @ 278' with 225 sacks of cement

0-70	Sand & Gravel
70-405	Shale & Shells
405-1117	Red Bed, Shale & Shells
1117-1315	Shale & Lime
1315-2080	Shale & Shells
2080-2250	Lime
2250-2415	Lime & Shale
2415-2540	Lime
2540-3858	Lime & Shale
3858-4145	Lime
4145-4335	Lime & Shale
4335-4350	Lime
4350-4379	Lime & Chat
4379-4426	Lime
4426-4435	Lime & Shale

11-4-65
RECEIVED
 STATE CORPORATION COMMISSIONER

NOV 4 1965


CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

I, Donald C. Slawson, of the Slawson Drilling Company, Inc., upon oath state that the above and foregoing is a true and correct copy of the log of the Fertig 'A' #1 well.


 DONALD C. SLAWSON

Subscribed and sworn to before me this 28th day of October, 1965.


 Ella Priess, Notary Public

My Commission Expires:
 August 25, 1968