

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21,224-0000

LEASE NAME Fertig

WELL NUMBER #3-14

SPOT LOCATION NE NW SE

SEC. 14 TWP. 24S RGE. 17 (W)

COUNTY Edwards

Date Well Completed 11-17-84

Plugging Commenced 11-17-84

Plugging Completed 11-17-84

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F. G. Holl

ADDRESS 6427 East Kellogg  
Wichita, Kansas 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 1

Is ACO-1 filed?                      If not, is well log attached? Yes

Producing formation                      Depth to top                      bottom                      T.D. 4485'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	298'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from    feet to    feet each set.

Filled hole with heavy mud.

Plugged with 50 sacks at 1080'; 70 sacks at 540'; olug, bridge and 10 sacks at 40'. 15 sacks in rathole and 10 sacks in mousehole.

Used 60/40 Pozmix, 2% gel and 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129, Sterling, Kansas 67579

11-21-84

RECEIVED

STATE OF KANSAS COUNTY OF RICE, ss. STATE CORPORATION COMMISSION

F. A. Wuellner (employee of operator) or NOV 21 1984  
(operator) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God. CONSERVATION DIVISION  
Wichita, Kansas  
STERLING DRILLING COMPANY

(Signature) F. A. Wuellner  
F. A. Wuellner, Secretary

(Address) P. O. Box 129, Sterling, Kansas 67579



SUBSCRIBED AND SWORN TO before me this 19th day of November, 1984.

Agnes D. Wurst  
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-85

## STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - FERTIG #3-14

Located: NE NW SE, Section 14-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 10, 1984

COMPLETED: November 17, 1984

TOTAL DEPTH: 4485'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 125 Sand and Clay	Ran 7 joints 8 5/8" OD casing. 284.31'
125 - 1980 Shale	pipe set at 298' K.B. Cemented with 210 sacks Common with 2% gel and 3% cc.
1980 - 2110 Shale and Lime Stringers	Plug down at 1:30 PM, 11-10-84, by Howco.
2110 - 4485 Lime and Shale	Plugged.

Deviation Surveys: 1 1/4° at 2163'  
1 1/4° at 4370'

RECEIVED  
STATE CORPORATION COMMISSION

NOV 21 1984

CONSERVATION DIVISION  
Wichita, Kansas

11-21-84