

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.--82-3-117

API NUMBER 15-047-20,369-0000

LEASE NAME Chalk

WELL NUMBER 1-14

 Ft. from S Section Line

 Ft. from E Section Line
 SE SE SW

SEC. 14 TWP. 24 RGE. 17W (E) or (W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 3-8-88

Plugging Completed 4-6-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR F.G. Holl Company

6427 E. Kellogg

ADDRESS Wichita, Kansas 67207

PHONE#(310) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4504'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	259'	none
				4-1/2"	4508'	2211'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4275' and 4 sacks cement. Shot pipe @2420', 2211', pulled a total of 68 joints of 4-1/2" casing. Plugged surface with 4 hulls, 10 gel, 50 cement, 10 gel, 1 hull, released plug and 130 cement.
Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 7th day of April, 19 88

James Hoover
 Notary Public

My Commission Expires:



4-8-88
 APR - 8 1988

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOC - - - - - CHALK #1
Located: SE SE SW, Section 11-21S-17W, Edwards County,
Kansas

OWNER: F. G. Moll, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 8, 1978
COMPLETED: April 16, 1978

TOTAL DEPTH: 4510'

LOC	DESCRIPTION	CASING RECORD
0 - 190	Sand and Clay	Ran 6 joints used 28 1/2" 5/8" casing, 246.16' set at 259' T. B. with 225 sacks 60/40 Pozmix with 3% cc. Plug down at 2:15 PM, 4-8-78, by Howco.
190 - 263	Shale	
263 - 320	Clay and Shale	
320 - 1027	Shale, Sand and Red Bed	Ran 139 joints new 10.5", 4 1/2" casing, 4499.17' set at 4508' T. B. with 50 sacks Howco Light, followed by 100 sacks Pozmix with 2% gel and 18% salt and 5% gilsonite and 1/8" flocele and 1/8" tufiber and 3/4% CFR-2 per sack. 250 gal. mud flush and 20 bbl. salt flush ahead of cement. Plug down at 5:00 PM, 4-16-78, by Howco.
1027 - 1117	Shale	
1117 - 1132	Anhydrite	
1132 - 1780	Shale and Shells	
1780 - 2160	Salt, Shale, Lime Strgs.	
2160 - 4510	Lime and Shale	

2-18-88

COMMISSION
FEB 18 1988
CONSERVATION DIVISION