

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
290 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21,349-0000

LEASE NAME Miller "B"

WELL NUMBER 3-14

4950 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 14 TWP. 24S RGE. 17W (W)

COUNTY Edwards

Date Well Completed 9-19-89

3:00 PM

Plugging Commenced 9-19-89

4:30 PM

Plugging Completed 9-19-89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F. G. Holl Company

P. O. Box 780167

ADDRESS Wichita, Kansas 67278-0167

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well Dry Hole

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-19-89 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed?            If not, is well log attached? Yes

Producing Formation            Depth to Top            Bottom            T.D. 4520'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	307'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from     feet to     feet each set.

Filled hole with heavy mud. Plugged with 50 sacks at 1150'; 40 sacks at 330';  
15 sacks 50' to surface. 15 sacks in rathole. Used 60/40 Pozmix with 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

P. O. Box 129

Address Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

Richard L. Mead

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STERLING DRILLING COMPANY

(Signature) Richard L. Mead

Richard L. Mead, President

(Address) P. O. Box 129, Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 20th day of September, 1989

Agnes D. Wurst  
Agnes D. Wurst, Notary Public

My Commission Expires: 4-26-93



RECEIVED

9-21-89

SEP 21 1989

CONSERVATION DIVISION  
Wichita, Kansas

# STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - MILLER "B" 3-14

Located: NW NE NW, Section 14-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 13, 1989

COMPLETED: September 19, 1989

TOTAL DEPTH: 4520'

LOG

CASING RECORD

0 - 160 Sand and Clay  
 160 - 430 Shale and Red Bed  
 430 - 1040 Shale, Sand, Red Bed  
 1040 - 1119 Shale  
 1119 - 1138 Anhydrite  
 1138 - 4520 Lime and Shale

Ran 7 joints 8 5/8" casing. 293.86'  
 pipe set at 307' K.B. Cemented with  
 225 sacks 60/40 Pozmix, 2% gel, 3% cc.  
 Plug down at 12:45 PM, 9-13-89, by  
 B. J. Titan.

Plugged.

Deviation Survey: 3/4° at 4395'