

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-047-21120-0000

API NUMBER \_\_\_\_\_

LEASE NAME Fertig

WELL NUMBER 2

\_\_\_\_\_ Ft. from S Section Line

\_\_\_\_\_ Ft. from E Section Line

SEC. 14 TWP. 24 RGE. 17W (E) or (W)

COUNTY Edwards

Date Well Completed \_\_\_\_\_

Plugging Commenced 8-21-90

Plugging Completed 10-10-90

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR F.G. Holl Company

ADDRESS P.O. Box 158 Belpre, Ks. 67519

PHONE#(316) 995-3171 OPERATORS LICENSE NO. 5056

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)  
 by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 4490'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	264'	none
				4 1/2"	4477'	2228'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Sanded bottom to 4370', ran 4 sacks cement. Shot pipe @2613', 2411', 2228'. Plugged with 300# hulls, 10 gel, 50 cement, 10 gel, 100# hulls, 125 sacks 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 60507

Address P.O. Box 347 Chase, Kansas 67524 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company OCT 16 1990

STATE OF Kansas COUNTY OF Rice, ss. CONSERVATION DIVISION  
 Wichita, Kansas

R. Darrell Kelso

(Employee of Operator) or (Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 17 day of Oct., 19 90

My Commission Expires: \_\_\_\_\_



Notary Public

WELL LOG -----Fertig 2-14

Located: NE SE SE, Section 14-24-17W  
SE Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Co.

COMMENCED: October 2, 1983

COMPLETED: October 9, 1983

TOTAL DEPTH: 4490 feet

LOG

0 -	90'	Surface soil & sand
90 -	267'	Shale
267 -	1118'	Shale & Red Beds
1118 -	1134'	Anhydrite
2015 -	4490'	Lime & Shale

CASING

Ran 6 joints of new 24# 8 5/8" casing. Talled 252.33' set at 264' KB. Cemented with 210 sx 60-40 Pozmix + 3% cc. Plug down at 11:15 AM 10-2-83 By Howco.

Ran 109 joints 10.5# 4 1/2" casing. 4468.05' set at 4477' KB. Cemented with 100 sacks Lite and 125 sacks 50-50 Pozmix and our Regular additives. Plug down at 9:45 AM 10-9-83 By Howco

DEVIATION SURVEYS

1/3° at 2203'  
1° at 4392'

RECEIVED  
STATE CORPORATION COMMISSION

MAY 25 1990

CONSERVATION DIVISION  
Wichita, Kansas

5-25-90