

KCC

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 083-21,227-0000

LEASE NAME Benish

WELL NUMBER 7-16

3630 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 16 TWP. 24 RGE. 22 (E) or (W)

COUNTY Hodgman

Date Well Completed 1-20-86

Plugging Commenced 2-6-91

Plugging Completed 2-6-91

RECEIVED
STATE OF KANSAS
2-21-91
FFR 21 1991

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Robert Schulein & Associates

ADDRESS 1776 Lincoln St. #811 Denver, CO 80203

PHONE# (303) 839-5495 OPERATORS LICENS: NO. 6785

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-6-91 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-i filed? yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 4660' Bottom 4670' T.D. 4670'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-------------|---------|---------|-------|--------|--------|------------|
| Mississippi | oil | surface | 413' | 8 5/8" | 413' | -0- |
| | | surface | 4660' | 5 1/2" | 4660' | -0- |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. 400# cottonseed hulls & 40 sax cement from TD to 4270' - gel from 4270' to 1550' - 60 sax cement from 1550' to surface. Pumped 8 sax cement down annulus - pressure to 300 psi - head was leaking. Use 128 sax 60/40 poz mix + 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Plains Well Service License No. 4072

Address Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Robert Schulein & Associates


STATE OF _____ COUNTY OF _____, ss.

Carl W. Durr (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carl W. Durr

(Address) R.R. #1 Box 16A-3 Milton, KS 67106

SUBSCRIBED AND SWORN TO before me this 20th day of February, 19 91



My Commission Expires: 4-19-92 Wendy S. Rorabaugh Notary Public

Joan Finney
Governor

Keith R. Henley
Chairman

Rich Kowalewski
Commissioner

Jack Shriver
Commissioner

Judith McConnell
Executive Director



15-083-21227-0000
Kansas Corporation Commission

MEMORANDUM

TO: Well File
FROM: Steve Durrant
DATE: 2/13/91
SUBJECT: Benish #7-16
N/2 SW NE 16-24S-22W
Hodgeman County

Duane Rankin gave plugging orders on this well, which are different than what was actually done. There is an intermediate plug missing that was discussed with Carl Durr but never placed in the well.

With the DV tool at 1535' and 450' sx of cement used, the backside was circulated back to the surface.

I believe this well is plugged adequately, and I do not recommend any further action be required.

Kansas Corporation Commission
District Office No. 1
304 W. McArtor
Dodge City, KS 67801
(316) 225 - 6760
Field Supervisor - Steve Durrant

FEB 15 1991

CLERK OF DISTRICT COURT
WICHITA, KANSAS