

15-083-20147-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Hodgeman County. Sec. 11 Twp. 24S Rge. XXI 22 (W)  
Location as "NE/CNW/SW" or footage from lines C NE NE  
Lease Owner Pickrell Drilling Company  
Lease Name Hall "M" Well No. 1  
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 22 1970  
Application for plugging filed December 22 1970  
Application for plugging approved December 22 1970  
Plugging commenced December 22 1970  
Plugging completed December 22 1970  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4665 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	278	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom Plug @ 600' w/30 sacks, Second Plug @ 270' w/30 sacks,  
Top Plug @ 45' w/10 Sacks Cement.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 30 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
C. W. Sebitts  
705 Fourth National Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of December, 19 70



Esther Lamone  
Notary Public.

My commission expires January 19, 1973

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Building  
Wichita, Kansas 67202

Rotary Drilling Commenced 12/10/70

Rotary Drilling Completed 12/22/70

LOCATION: Hall "M" No. 1, C NE NE Sec. 11-24S-22W  
Hodgeman County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: Run 10 Jts. 8-5/8" surface casing set @ 278' KB. Cemented with  
150 Sacks Cement. Completed 8:00 P.M. Circulated.

No oil string run. D & A, Plugged 8:30 A.M. December 22, 1970.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40	Clay & Shale	<u>C.F.S.</u>
170	Shale & Shells	4200
190	Sand	4251
279	Shale & Shells	4360
570	Shale & Sand	4405
795	Red - Beds	4425
805	Blain	4453
915	Red Beds	4470
1085	Sand	4590
1385	Shale - Shells	4615
1439	Shale	4635
1473	Anhydrite	4650
1920	Shale & Shells	4665
2290	Shale & Lime	
2615	Lime & Shale	
2890	Lime	
3525	Lime & Shale	
3660	Shale & Lime	
3981	Lime & Shale	<u>Slope Tests</u>
4650	Lime	2000
4665	Mississippian, RTD	2500
		3000
		3500
		4000
		4500

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 30 1970  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.


PICKRELL DRILLING COMPANY  
By [Signature]  
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 28th day of December, 1970, before me the undersigned, a Notary Public, in and for

County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact, and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.



My commission expires: January 19, 1973

Esther Lamone  
Esther Lamone Notary Public